

P:\MUS\87541\DESIGN\RIGHT\_OF\_WAY\PLAN\_SHEETS\ 20.92\87541\_0001\_RTS.dgn 01/10/11

# UTILITY OWNERS

AT & T OHIO  
160 NORTH SIXTH STREET  
ZANESVILLE, OHIO 43701  
ATTN: SANDY RANDOLPH  
740-454-3455

GUERNSEY MUSKINGUM ELECTRIC COOPERATIVE, INC.  
17 SOUTH LIBERTY STREET  
NEW CONCORD, OHIO 43762  
ATTN: JOHN MARSHALL  
740-826-7661


MUSKINGUM COUNTY WATER  
P.O. BOX 2005  
ZANESVILLE, OHIO 43701  
ATTN: DON MADDEN  
740-607-8743

TIME WARNER CABLE  
3760 INTERCHANGE DRIVE  
COLUMBUS, OHIO 43204  
ATTN: TERRY ALLEN  
614-255-6349

## NOTE:

THE LOCATION OF THE UNDERGROUND UTILITES SHOWN ON THE PLANS ARE OBTAINED FROM THE OWNER OF THE UTILITIES AS REQUIRED BY SECTION 153.64 O.R.C.

## STRUCTURE KEY



## LEGEND:

WL = FEE SIMPLE WITH LIMITATION OF ACCESS  
WD = WARRANTY DEED  
BS = BILL OF SALE  
PRW = PROPERTY RIGHT FEE SIMPLE  
SH = STANDARD HIGHWAY EASEMENT  
LA = LIMITED ACCESS EASEMENT  
T = TEMPORARY EASEMENT  
SL = SLOPE EASEMENT  
S = SEWER EASEMENT  
CH = CHANNEL EASEMENT

FL = FLOW EASEMENT  
U = UTILITY EASEMENT  
A = AERIAL EASEMENT  
PRE = PROPERTY RIGHT  
SC = SCENIC EASEMENT  
V = IN NAME OF ANOTHER STATE AGENCY, LPA, ETC.  
R = SPECIAL RESERVATION  
WA = WORK AGREEMENT  
SA = SPECIAL AGREEMENT AND WAIVER OF DAMAGES

## CONVENTIONAL SYMBOLS

|                            |                |                       |                             |
|----------------------------|----------------|-----------------------|-----------------------------|
| County Line                | -----          | Ditch / Creek (Ex)    | -----                       |
| Township Line              | -----          | Ditch / Creek (Pr)    | -----                       |
| Section Line               | -----          | Tree Line (Ex)        | ~~~~~                       |
| Corporation Line           | ----- or ----- | Ownership Hook Symbol | Example                     |
| Fence Line (Ex)            | ----- (Pr)     | Property Line Symbol  | Example                     |
| Center Line                | -----          | Break Line Symbol     | Example                     |
| Right of Way (Ex)          | ----- Ex R/W   | Tree (Pr)             | Tree (Ex) Shrub (Ex)        |
| Right of Way (Pr)          | ----- R/W      | Tree (Remove)         | Shrub (Remove)              |
| Standard Highway Ease.(Ex) | ----- Ex SH    | Evergreen (Ex)        | Stump                       |
| Temporary Right of Way     | ----- TMP      | Evergreen (Remove)    | Stump (Remove)              |
| Channel Ease. (Pr)         | ----- CH       | Wetland (Pr)          | Grass (Pr) Aerial Target    |
| Utility Ease. (Ex)         | ----- Ex U     | Post (Ex)             | Mailbox (Ex) Mailbox (Pr)   |
| Railroad                   | ----- or ----- | Light (Ex)            | Telephone Marker (Ex) TEL   |
| Guardrail (Ex)             | ----- (Pr)     | Fire Hydrant (Ex)     | Water Meter (Ex)            |
| Construction Limits        | -----          | Water Valve (Ex)      | Utility Valve Unknown (Ex.) |
| Edge of Pavement (Ex)      | -----          | Telephone Pole (Ex)   | Power Pole (Ex)             |
| Edge of Pavement (Pr)      | -----          | Light Pole (Ex)       |                             |
| Edge of Shoulder (Ex)      | -----          |                       |                             |
| Edge of Shoulder (Pr)      | -----          |                       |                             |

# STATE OF OHIO DEPARTMENT OF TRANSPORTATION

## RIGHT OF WAY LEGEND SHEET MUS-146-20.92 PART 1

### SECTION 7, R12W, T13N WAYNE TOWNSHIP MUSKINGUM COUNTY

#### INDEX OF SHEETS:

|                                    |     |
|------------------------------------|-----|
| CENTERLINE PLAT                    | 2   |
| PROPERTY MAP                       | 3   |
| SUMMARY OF ADDITIONAL RIGHT OF WAY | 4   |
| RIGHT OF WAY DETAIL SHEETS         | 5-8 |

#### PROJECT DESCRIPTION

IMPROVE ROADWAY ALIGNMENT AND REPLACE EXISTING SINGLE SPAN CONCRETE BEAM BRIDGE WITH A CONTINUOUS THREE SPAN CONCRETE SLAB BRIDGE ON CAPPED PILE ABUTMENTS AND PIERS.

#### PLAN PREPARED BY:

FIRM NAME: ODOT, DISTRICT 5  
PLANS PREPARED BY: CHUCK PRICE & CANDY SHOEMAKER  
FIELD REVIEW BY: 07/18/11  
OWNERSHIP VERIFIED BY: CHARLES PRICE, JR.  
DATE COMPLETED: 01/10/11

#### UNDERGROUND UTILITIES

CONTACT BOTH SERVICES  
CALL TWO WORKING DAYS  
BEFORE YOU DIG

CALL  
1-800-362-2764  
(TOLL FREE)  
OHIO UTILITIES PROTECTION SERVICE  
NON-MEMBERS  
MUST BE CALLED DIRECTLY

OIL & GAS PRODUCERS PROTECTIVE  
SERVICE CALL: 1-800-925-0988

I, Charles W. Price, Jr., P. S. have conducted a survey of the existing conditions for the Ohio Department of Transportation in June, 2010. The results of that survey are contained herein.

Underground utility locations are shown for informational purposes only. Though they are believed to be accurate, their location is as marked on the ground by the utility company per OUPS Confirmation Number A017400724 and those markings subsequently being surveyed as a part of this project.

The horizontal coordinates expressed herein are based on the Ohio State Plane Coordinates system, NAD 83, South Zone.

As a part of this project I have reestablished the locations of the existing property lines and centerline of existing Right of Way for property takes contained herein.

As a part of this project I have established the proposed property lines, calculated the Gross Take, present roadway occupied (PRO), Net Take and Net Residue; as well as prepared the legal descriptions necessary to acquire the parcels as shown herein.

As a part of this work I have set monuments at the proposed property corners, and other points shown herein.

The iron pins and caps will be 3/4" x 30" rebar with aluminum cap stamped "Odor R/W District 5". All of my work contained herein was conducted in accordance with Ohio Administrative Code 4733-37 commonly known as "A Minimum Standards for Boundary Surveys in the State of Ohio" unless so noted.

The words I and my as used herein are to mean that either myself or someone working under my direct supervision.

Charles W. Price, Jr., Professional Land Surveyor # 7825

Date: 1-18-11

