

SUMMARY OF QUANTITIES

F.E.R.A

PROJECT No

Township Road 285
Hopewell Twp.
Muskingum County.

10
10

SUMMARY OF WEARING SURFACE	
13200 L x 12'W x 3"T.	1985 TONS.

SUMMARY OF EXCAVATION & EMB'K.					
FROM STA.	TO STA.	Exc. Cu.Yds.	EMB. Cu.Yds.	EMB. 15% Cu.Yds.	WASTE Cu.Yds.
0+00	9+00	3751	264	317	3434
9+00	13+00	3145	339	1067	2078
13+00	27+00	3405	503	210	2705
27+00	36+00	2332	236	283	2049
Sub. Total		12633	1302	2277	10356
36+00	Rd #286	5075	1500	1800	3275
Total		17708	3397	4077	13631

LENGTH OF PROJECT			
From Sta.	To Sta.	Length Project.	NOTE: No additions or deductions.
0 + 00	36 + 00	3600 Lin. Feet	
36 + 00	Rd #286	9600 " "	
	Total	13200 " "	
		= 2 1/2 Miles	

SUMMARY OF QUANTITIES FOR STRUCTURES UNDER 20' SPAN										
Station	CONCRETE PIPE						1-5½ CONC.	1-7½ CONC.	Rip Rap	Remarks.
	12" Lin. Ft.	15" Lin. Ft.	18" Lin. Ft.	24" Lin. Ft.	30" Lin. Ft.	36" Lin. Ft.				
6 + 66	30								3	Build new
13 + 52		32							3	"
21 + 03	28									"
Sec. "B"				64					6	"