

**Project No. 271**

The Computerized Plant System shall also have an audible alarm system, which notifies the plant operator when the amount of bitumen, aggregate, or reclaimed pavement being mixed into the asphalt concrete is outside the tolerances established by the Contractor's Quality Control Supervisor. The plant operator shall make appropriate adjustments when production is outside the tolerances.

When 446 or 448 Asphalt Concrete is being produced in an asphalt plant with an approved Computerized Plant System and the MTD has been established for the JMF, the frequency of performing AC Gauge tests and gradation analyses as specified in 441.10 shall be modified to one test every 4 hours of production.

All asphalt concrete produced on January 1, 1993 and thereafter shall have the following additional information printed out for both batch and drum mix plants:

- a. JMF Number
- b. percent bitumen in the reclaimed pavement (if used) to the nearest 0.1 percent
- c. percent virgin bitumen to the nearest 0.1 percent

and the following additional information shall be printed out for batch plants:

- a. tare weight of the bitumen scale
- b. tare weight of the aggregate scale
- c. moisture content of the reclaimed pavement (if used)

**Design Requirements for Plant Mix Pavements**

On this project, all 301, 402, 403, 404, 412, 446 and 448 materials shall be designed for Light traffic volumes.

**SPECIALTY ITEMS (108.01)**

The following items in this contract, if sublet, will be treated as "Specialty Items": 517, 606, 642, 645

**Post Construction Meeting**

Approximately 10 days after the final inspection, the Engineer may conduct a post construction meeting to critique the contract documents (i.e. plans, proposal). The meeting will be at a time and place as determined by the Engineer.

The Contractor shall attend and be prepared to discuss any aspect of the project including portions of the project sublet. The Engineer shall contact the Design agency or Consultant and the local government agency to request a representative attend this meeting.

Minutes shall be taken by the Engineer at this meeting. Copies of these minutes shall be distributed to the following:

- Contractor
- Design agency or Consultant
- Bureau of Location & Design or Maintenance or Traffic
- Bureau of Construction
- District Construction
- District Location and Design
- Local Government Agency, if applicable

For projects which will take two or more full construction seasons to complete, an additional construction meeting may be held at approximately the mid point of the Contract.

The cost of attending this meeting shall be incidental to the Contract.

**614.03 (c) Warning Lights**

Steady burn warning lights shall not be required for drums or barricades.