

GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

5
14

MUSKINGUM COUNTY
MUS-156-2.02

ITEM	QUANTITIES			UNIT	DESCRIPTION
	Participation By The United States of America	Participation By The State of Ohio	Totals for Project		
	Schedule A	Schedule B	Schedule A+B		
E-1	1,067	145	1,212	Cu. Yd.	ROADWAY Roadway Excavation, Method A, Unclassified
E-1	5,436	1,040	6,476	Cu. Yd.	Road Embankment, Method A
E-1	2,700	300	3,000	Cu. Yd.	Compacted Subgrade
E-11	32.43	5.77	38.20	M-Gal.	Water
E-12	130		130	Lin. Ft.	Pipe Removed, 15 inch and under
E-12	33		33	Lin. Ft.	Pipe Removed over 15 inch
I-8	10		10	Each	Monument Assemblies
L-9	7,491	1,500	8,991	Sq. Yd.	Seeding and Protecting
L-9	0.67	0.14	0.81	Ton	Commercial Fertilizer
L-9	3.35	0.70	4.05	Ton	Agricultural Liming Materials
T-10	918		918	Cu. Yd.	Traffic Compacted Surface Course
Special	18.36		18.36	Ton	Calcium Chloride
Special	Lump		Lump	Lump	Relocating or adjusting Existing Power Lines
Special	Lump		Lump	Lump	Maintaining Traffic
					DRAINAGE
E-2	36		36	Cu. Yd.	Excavation for Structures, Unclassified
I-1	30		30	Lin. Ft.	12 inch Pipe for Driveway
I-1	34		34	Lin. Ft.	24 inch Pipe for Driveway
I-2		50	50	Lin. Ft.	8 inch Storm Sewer under Pavement
I-2	85		85	Lin. Ft.	12 inch Storm Sewer under Pavement
I-4		624	624	Lin. Ft.	6 inch Pipe Underdrains
I-5		2	2	Each	8 inch Pipe Specials for Storm Sewer under Pavement
I-9	147	84	231	Lin. Ft.	Stone Underdrains (No. 2)
S-1	1.72		1.72	Cu. Yd.	Concrete for Structures
S-27	54	10	64	Lin. Ft.	48 inch Pipe for Roadway Culvert Section M-6.6(b)
L-10	198		198	Sq. Yd.	Sodding
					PAVEMENT
B-19	316.67	33.33	350	Cu. Yd.	Aggregate Base Course
B-219	225.00	25.00	250	Cu. Yd.	Waterproofed Aggregate Base Course
I-18	41		41	Cu. Yd.	Stabilized Crushed Aggregate for Driveways
I-22	416.50	50.09	466.59	Cu. Yd.	Subbase
T-30	1,140.00	120.00	1,260	Gallon	Bituminous Prime Coat
T-35	93.75	10.41	104.16	Cu. Yd.	Asphaltic Concrete Surface Course

REVISION	DATE	DESCRIPTION	BY
U. S. ARMY ENGINEER DISTRICT, HUNTINGTON CORPS OF ENGINEERS HUNTINGTON, W. VA.			
DRAWN BY: F.H.S.		LICKING RIVER DILLON RESERVOIR PROJECT	
TRACED BY: CRW		READJUSTMENT OF OHIO STATE ROUTE NO.156 (Section 2)	
CHECKED BY: JAY		DATE September 1959	
SUBMITTED BY: Elmer S. Barrett		APPROVED: Steven Malovich	
ELMER S. BARRETT ASSOCIATES		COL. C.E. DISTRICT ENGINEER	
RECOMMENDED: James J. Barrett			
CHIEF ENG. DIV.			
ELMER S. BARRETT ASSOCIATES CONSULTING ENGINEERS CHILLICOTHE, OHIO		SCALE: DRAWING NUMBER 027f-UD12-68/5 SHEET 5 of 14	