TYPE CODE 6201

GENERAL SUMMARY

ITEM	QUANTITIES: TOTAL Participation By County & Federal	TOTAL Participation By State & Federal	TOTAL	UNIT	DESCRIPTION
					ROADWAY
E-1	2,911	1,177	4,088	S.Y.	Compacted Subgrade
E-1	708	347	1,244	C.Y.	Roadway Excavation, Method "B" as per plan.
E-4	11,060	2,740	13,800	C.Y.	Borrow
E-8	0	46	46	S.Y.	Removal and Disposal of Existing Pavement
E-8	0	232	232	L.F.	Removal and Disposal of Existing Curb
E-9	Lump	Lump	Lump	Lump	Removal of Trees and Stumps
E-11	59	18	77	M-Gal.	Water
I-15	450	425	875	L.F.	Guard Rail, Steel Beam Standard Type (Deep)
L-9	6,252	3,085	9,337	S.Y.	Seeding and Protecting, as per plan
L-9	0.56	0.28	0.84	Ton	Commercial Fertilizer (12-12-12)
L-9	2.81	1.39	4.20	Tons	Agricultural Liming Material
M-10	3	0	3	Tons	Calcium Chloride Furnished and Applied for Maintaining Traffic.
T-10	150	0	150	C.Y.	Traffic Compacted Surface Course for Maintaining Traffic
					DRAINAGE
E-2	63	93	156	C.Y.	Excavation for Structures
E-3	1,225	495	1,720	C.Y.	Channel Excavation
E-12	0	86	86	L.F.	Pipe Removed, 15" and Under
I-2	0	36	36	L.F.	12" Class "B" Storm Sewers
I-2	0	32	32	L.F.	12" Class "B" Storm Sewers Under Pavement or Approaches
I-2	52	0	52	L.F.	15" Storm Sewers Sec. M 6.4(c)
I-2	0	20	20	L.F.	12" Outlets for Storm Sewers, Sec. M-6.4(c)
I-5	0	1	1	Ea.	12" Pipe Specials for outlets for storm sewers, Sec. M-6.4(c)
I-5	2	0	2	Ea.	15" Pipe Specials for storm sewers, Sec. M-6.4(c)
I-9	479	201	680	L.F.	Stone Underdrains, No. 2
I-10	281	2	283	S.Y.	Riprap, Grout filled
I-10	224	93	317	C.Y.	Dumped Rock Channel Protection
S-1	13.0	23.8	36.8	C.Y.	Class "E" Concrete for Structures
S-27	70	0	70	L.F.	48" Pipe for Roadway Culverts, Sec. M-6.6(b)
S-28	58	0	58	L.F.	9'-6" x 6'-5" Sectional Corrugated Metal Structures, Sec. M 6.4 (g), 10-8 Gage.
S-28	0	106	106	L.F.	15'-10" x 9'-10" Sectional Corrugated Metal Structures, Sec. M 6.4 (g), 7-5 Gage
S-24	Lump	0	Lump	Lump	Removal of Existing Structure
					PAVEMENT
B-19	520	263	783	C.Y.	Aggregate Base Course
B-35	0	975	975	L.F.	Sealing Vertical Face of Existing Pavement
B-35	141	120	261	C.Y.	Asphaltic Concrete Leveling Course (85-100)
T-35	106	43	149	C.Y.	Asphaltic Concrete Surface Course Type "C" (85-100)
T-30	1,197	496	1,693	Gal.	Bituminous Prime Coat: Sec. M 5.7, RT-2 or RT-3
I-21	0	39	39	S.Y.	Portland Cement Concrete Median Pavement, Standard Type 2, Modified as per plan.
I-22	337	203	540	C.Y.	Subbase
	Lump	Lump	Lump	Lump	Construction Layout Stakes
	Lump	Lump	Lump	Lump	Maintaining Traffic

FED. RD. DIVISION	STATE	PROJECT	TYPE FUNDS
2	OHIO	S-522(3)	

MUSKINGUM COUNTY
CO. RD. 55

RECEIVED FEB 15 1961