

GENERAL SUMMARY

QUANTITIES		FHWA REGION	STATE	PROJECT	
CALCULATED		5	OHIO		
CHECKED					

MUSKINGUM COUNTY
FALLS TOWNSHIP
CITY OF ZANESVILLE
MUS-60-2057 MAPLE AVENUE

8

ITEM NO.	CITY AND FEDERAL	STATE AND FEDERAL	TOTAL	UNIT	DESCRIPTION
ROADWAY					
201		L.S.	L.S.	L.S.	Clearing And Grubbing
202				L.F.	Curb And Gutter Removed
202	2.9		2.9	C.Y.	Concrete Masonry Removed
202		285	285	L.F.	Pipe Removed, 24" And Under
203				C.Y.	Excavation Not Including Embankment Construction
203				C.Y.	Embankment
203				S.Y.	Subgrade Compaction
604				Each	Manumnt Assembly, Standard
609				Each	Curb Ramps, Standard
609				S.F.	4" Concrete Walk
616				Ton	Calcium Chloride
616				MGal	Water
PAVEMENT					
301				C.Y.	Bituminous Aggregate Base, AC-20, Or RT-11 Or RT-12
304				C.Y.	Aggregate Base
310				C.Y.	Subbase, Grading A
402				C.Y.	Asphalt Concrete, AC-20
403				C.Y.	Asphalt Concrete, AC-20, Preleveling Course
404				C.Y.	Asphalt Concrete, AC-20
404				C.Y.	Asphalt Concrete, AC-20 (Driveways)
407				Gal.	Tack Coat: RC-250, MS-2, RS-1, SS-1 Or SS-1h
407				Ton	Cover Aggregate
408				Gal.	Bituminous Prime Coat: MC-30, MC-70, Primer 20, RT-2 Or RT-3
452				S.Y.	6" Plain Portland Cement Concrete Pavement
609				L.F.	Combination Curb And Gutter, Standard Type-2
609				L.F.	Curb, Standard Type-6
DRAINAGE					
602		.37	.37	C.Y.	Concrete Masonry
603	167	52	219	L.F.	12" Conduit, Type-B, 706.02
603		82	82	L.F.	15" Conduit, Type-B, 706.02
603		85	85	L.F.	18" Conduit, Type-B, 706.02
603		60	60	L.F.	21" Conduit, Type-B, 706.02
603	68		68	L.F.	30" Conduit, Type-B, 706.02
603	116	120	236	L.F.	12" Conduit, Type-C, 706.02
603		452	452	L.F.	18" Conduit, Type-C, 706.02
603		471	471	L.F.	21" Conduit, Type-C, 706.02
603		200	200	L.F.	4" Conduit, Type-E, 711.29
603		120	120	L.F.	6" Conduit, Type-E, 706.01, 706.02, 706.08, 711.29
603		46	46	L.F.	6" Conduit, Type-F

ITEM NO.	CITY AND FEDERAL	STATE AND FEDERAL	TOTAL	UNIT	DESCRIPTION
DRAINAGE CONT.					
604		2	2	Each	Standard No. 2-2-B Catch Basin
604		1	1	Each	Standard No. 3 Catch Basin
604	4	3	7	Each	Standard No. 3A Catch Basin
604	1		1	Each	Standard No. 4 Catch Basin With Grate-E
604		3	3	Each	Standard No. 6 Catch Basin
604	1		1	Each	Manhole Reconstructed To Standard No. 2-3 Catch Basin
604	1		1	Each	Manhole Reconstructed To Standard No. 2-4 Catch Basin
604	1		1	Each	Manhole Reconstructed To Grade (Sanitary)
604	1	1	2	Each	Standard No. 1 Manhole
604		2	2	Each	Standard No. 1 Manhole Using Catch Basin Grate Cover
EROSION CONTROL					
207				Each	Straw Or Hay Bales
207				S.Y.	Temporary Seeding And Mulching
601		4.8	4.8	C.Y.	Rock Channel Protection, Type-B, With Bedding
659				S.Y.	Repair Seeding And Mulching
659				S.Y.	Seeding And Mulching
659				Ton	Commercial Fertilizer (12-12-12)
659				MGal	Water
659				M/S.F.	Mowing
660				S.Y.	Sodding
667				S.Y.	Seeding And Silt Matting
614		L.S.	L.S.	L.S.	Maintaining Traffic
619		L.S.	L.S.	L.S.	Field Office
623		L.S.	L.S.	L.S.	Construction Layout Stakes