

GENERAL NOTES

PCB	11-87
ROB	11-87

FHWA REGION	STATE	PROJECT	
5	OHIO		

MUSKINGUM COUNTY
MUS - CR. 719

6
55

TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS AND THE FOLLOWING REQUIREMENTS;

THE CONTRACTOR WILL BE REQUIRED TO PROVIDE, ERECT, MAINTAIN (IN PROPER POSITION, CLEAN, LEGIBLE, AND IN GOOD WORKING CONDITION) AND REMOVE ALL SIGNS, SIGN SUPPORTS, BARRICADES, DRUMS, AND ALL OTHER TRAFFIC CONTROL DEVICES NECESSARY FOR THE MAINTENANCE OF TRAFFIC.

THE COST OF PROVIDING, INSTALLING, MAINTAINING AND REMOVING ALL TRAFFIC CONTROL DEVICES REQUIRED TO MAINTAIN TRAFFIC DURING CONSTRUCTION INCLUDING SIGNS, SIGN SUPPORTS, DRUMS, AND BARRICADES SHALL BE INCLUDED IN THE LUMP SUM PER ITEM 614 "MAINTAINING TRAFFIC".

THE CONTRACTOR SHALL MAINTAIN TRAFFIC AT ALL TIMES IN ACCORDANCE WITH THE REQUIREMENTS OF SPEC. 614. TWO-WAY FOUR LANE TRAFFIC SHALL BE MAINTAINED AT ALL TIMES ON US 22 EXCEPT FOR A SHORT PERIOD OF NOT MORE THAN 20 CONSECUTIVE DAYS WHILE CONNECTIONS TO C.R. 719 ARE COMPLETED. ONE LANE OF THE NORTHBOUND LANES ON EXISTING U.S. 22 MAY BE CLOSED IN ACCORDENCE WITH (C-21) OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

ACCESS TO ALL ADJOINING PROPERTIES AND EL CAMINO DR. SHALL BE MAINTAINED AT ALL TIMES. JUANITA DR. AT EL CAMINO DR. MAY BE CLOSED FOR 20 CONSECUTIVE DAYS WHILE CONNECTIONS ARE COMPLETED. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER FOR MAINTENANCE OF TRAFFIC.

ITEM 404	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	20 C.Y.
ITEM 410	TRAFFIC COMPACTED SURFACE TYPE A OR B	20 C.Y.
ITEM 616	WATER	10 M.GAL.
ITEM 616	CALCIUM CHLORIDE	1 TON

ALL OTHER WORK REQUIRED FOR TRAFFIC MAINTENANCE SHALL BE INCLUDED WITH PAYMENT FOR ITEM 614 MAINTAINING TRAFFIC.

ITEM 207 FILTER FABRIC FENCE

MATERIALS
FILTER FABRIC SHALL MEET THE REQUIREMENT OF ITEM 207.02.

CONSTRUCTION
THE BOTTOM OF THE FENCE SHALL BE BURIED 6" BELOW THE GROUND. THE FENCE SHALL BE HIGH ENOUGH TO RETAIN SEDIMENT LADEN WATER AND ADEQUATELY SUPPORTED TO PREVENT COLLAPSE OR BURSTING.

MAINTENANCE
THE FILTER FABRIC FENCE SHALL, AT THE DIRECTION OF THE ENGINEER, BE MAINTAINED TO BE FUNCTIONAL. THIS SHALL INCLUDE REMOVAL OF TRAPPED SEDIMENT AND REQUIRED CLEANING, REPAIR, AND/OR REPLACEMENT OF THE FILTER FABRIC.

PAYMENT
THE COST OF ALL MATERIALS, CONSTRUCTION, MAINTENANCE, AND REMOVAL REQUIRED SHALL BE PAID FOR UNDER ITEM 207, LIN. FT., FILTER FABRIC FENCE.