


STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.09	39.97	0.08	286.42	0.08	286.42
0+50	0.00	269.36	0.00	733.89	0.08	1020.31
1+00	0.00	523.24	0.00	1319.49	0.08	2339.80
1+50	0.00	901.81	0.00	2146.59	0.08	4486.39
2+00	0.00	1416.51	0.00	2956.49	0.08	7442.88
2+50	0.00	1776.50	0.00	3641.42	0.08	11084.30
3+00	0.00	2156.23	0.00	4708.92	0.08	15793.22
3+50	0.00	2929.41	0.00	5905.61	0.08	21698.83
4+00	0.00	3448.65	0.00	7307.84	0.08	29006.68
4+50	0.00	4443.82	0.00	8513.51	0.08	37520.18
5+00	0.00	4750.77	0.00	9046.88	0.08	46567.07
5+50	0.00	5019.87	0.00	9082.84	0.08	55649.91
6+00	0.00	4789.60	0.00	8243.76	0.08	63893.67
6+50	0.00	4113.66	0.00	6992.21	0.08	70885.88
7+00	0.00	3437.92	0.00	5682.59	0.08	76568.47
7+50	0.00	2699.28	0.00	4553.25	0.08	81121.72
8+00	0.00	2218.23	0.00	3544.87	0.08	84666.59
8+50	0.00	1610.23	0.00	2582.18	0.08	87248.77
9+00	0.00	1178.52	0.00	1932.26	0.08	89181.03
9+50	0.00	908.31	0.00	1562.43	0.08	90743.46
10+00	0.00	779.11	0.00	1415.01	0.08	92158.46
10+50	0.00	749.10	0.00	1604.34	0.08	93762.80
11+00	0.00	983.59	0.00	2932.42	0.08	96695.23
11+50	0.00	2183.43	0.00	5047.09	0.08	101742.32
12+00	0.00	3267.43	0.00	5327.42	0.08	107069.74
12+50	0.00	2486.19	0.00	3444.20	0.08	110513.94
13+00	0.00	1233.55	0.00	1787.35	0.08	112301.29
13+50	0.00	696.78	0.00	1016.73	0.08	113318.02
14+00	0.00	401.29	0.00	499.32	0.08	113817.34
14+50	0.00	137.97	35.54	133.47	35.62	113950.82
15+00	38.39	6.18	145.02	5.72	180.65	113956.54
15+50	118.24	0.00	314.55	0.00	495.19	113956.54
16+00	221.48	0.00	540.72	0.00	1035.91	113956.54
16+50	362.50	0.00	895.21	0.00	1931.12	113956.54
17+00	604.33	0.00	1371.32	0.00	3302.44	113956.54
17+50	876.70	0.00	1861.86	0.00	5164.30	113956.54
18+00	1134.11	0.00	2295.08	0.00	7459.38	113956.54
18+50	1344.58	0.00	2587.82	0.00	10047.20	113956.54
19+00	1450.27	0.00	2777.78	0.00	12824.98	113956.54
19+50	1549.73	0.00	2929.34	0.00	15754.31	113956.54
20+00	1613.95	0.00	2981.67	0.00	18735.98	113956.54
20+50	1606.26	0.00	3004.83	0.00	21740.81	113956.54
21+00	1638.96	0.00	3045.80	0.00	24786.61	113956.54
21+50	1650.50	0.00	3034.57	0.00	27821.18	113956.54
22+00	1626.83	0.00	2925.29	0.00	30746.47	113956.54
22+50	1532.48	0.00	2599.30	0.00	33345.78	113956.54
23+00	1274.77	0.00	2152.16	0.00	35497.94	113956.54
23+50	1049.57	0.00	1721.37	0.00	37219.30	113956.54
24+00	809.51	0.00	1192.45	0.00	38411.75	113956.54
24+50	478.33	0.00	782.26	0.00	39194.01	113956.54
25+00	366.51	0.00	634.61	0.00	39828.63	113956.54
25+50	318.87	0.00	589.95	0.00	40418.57	113956.54
26+00	318.27	0.00	689.58	0.00	41108.15	113956.54
26+50	426.47	0.00	872.60	0.00	41980.75	113956.54
27+00	515.94	0.00	1038.08	0.00	43018.82	113956.54
27+50	605.19	0.00	1211.43	0.00	44230.26	113956.54
28+00	703.16	0.00	1354.38	0.00	45584.64	113956.54
28+50	759.57	0.00	1406.04	0.00	46990.68	113956.54
29+00	758.96	0.00	1295.12	0.00	48285.80	113956.54
29+50	639.78	0.00	1029.39	0.00	49315.19	113956.54
30+00	471.97	0.00	761.04	0.00	50076.23	113956.54
30+50	349.95	0.00	583.90	0.00	50660.13	113956.54
31+00	280.66	0.00	468.10	0.00	51128.23	113956.54
31+50	224.90	0.00	404.92	0.00	51533.16	113956.54
32+00	212.42	0.00	343.79	0.00	51876.95	113956.54
32+50	158.87	0.00	285.37	0.00	52162.32	113956.54
33+00	149.33	0.00	269.04	0.00	52431.36	113956.54
33+50	141.24	0.00	234.16	0.00	52665.53	113956.54
34+00	111.66	0.00	180.08	0.00	52845.61	113956.54
34+50	82.83	0.00	131.75	0.01	52977.35	113956.54
35+00	59.46	0.01	0.00	0.00	52977.35	113956.54

The J&W Company
1218 St. Rt. 93 NE
New Lexington, Ohio 43764 (614) 342-5131



ENGINEERING
SURVEYING
RESOURCE
DEVELOPMENT

Zanesville-Muskingum County
Port Authority
Zanesville, Ohio 43701

SCALE	1" = 100'	CHECKED	TCW
DATE	8/31/99	APPROVED	
REVISED		CERTIFIED	
DRAWN	VP Jr.		

Dollar General
Access Road
Earthwork Volume Tables