



NOTES:

ROTATE ALL VALVES AS REQ'D. TO PROVIDE  
EASY ACCESS TO OPERATOR HANDLES.

OUTLET TEE, PIPING AND VALVES ARE INCLUDED  
IN UNIT PRICE BID FOR VARIOUS AIR RELEASE  
VALVE ASSEMBLIES.

CONTRACTOR SHALL FIELD LOCATE ALL AIR  
RELEASE VALVES AT THE ACTUAL HIGH POINT OF  
THE FORCE MAIN. LOCATIONS SHOWN IN PLAN  
AND/OR PROFILE DRAWINGS ARE ONLY  
APPROXIMATE

## COMBINED AIR RELEASE VALVE INSTALLATION

NOT TO SCALE

## SANITARY FORCE MAIN INSTALLATION

SCALE: NONE

NOTE:  
5'-6" IS THE NORMAL INSTALLATION DEPTH UNLESS NOTED OTHERWISE. THE DEPTH MAY BE LOWERED TO AVOID SANITARY HOUSE SERVICE LATERALS, STORM DRAINS, AND OTHER OBJECTS.  
THE FORCE MAIN SHALL BE CONSTRUCTED UNDER ALL WATER LINES BY A MINIMUM OF 1'-6"

[illegible]

## GAMBRO HEALTHCARE LIFT STATION & FORCE MAIN

## MISCELLANEOUS DETAILS

DATE	October 2003
JOB No.	14572464
DRAWN	MAL
CHECKED	FJS
SCALE	NONE