

3. Carrier Pipe. Carrier pipe installed in encasement pipe shall be restrained joint unless otherwise noted. Carrier pipe shall extend a minimum of 2 feet beyond each end of the encasement pipe.
4. Carrier Pipe Supports. After the encasement pipe is installed, the carrier pipe shall be installed in the encasement pipe by means of heavy duty polyethylene or coated steel insulators with skids. Carrier pipe supports shall be furnished on each side of the pipe joint. Provide a minimum of 4 supports per pipe section or at 6-foot spacing, whichever provides greater support. Provide end seals for encasement and carrier pipe. End seals shall be rubber boot type coupling with stainless steel bands as manufactured by Fernco or equal.

END OF SECTION