

GENERAL NOTES

WALL RECONSTRUCTION AREA

THE WALL RECONSTRUCTION AREA IS WHERE A PART OF THE OLD RETAINING WALL IS MISSING. THE INTENT OF THIS PART OF THE PROJECT IS TO POUR A NEW WALL TO FILL IN THE AREA OF THE MISSING WALL. (SEE DETAIL SHEET NO. 28)

ITEM 510- DOWEL HOLES

#5 DOWELS SHALL BE PLACED AT 2' CENTERS ALONG THE EXISTING WALL AS PER THE WALL RECONSTRUCTION AREA DETAIL. THIS WORK SHALL BE DONE IN ACCORDANCE WITH ODOT ITEM 510; IN ADDITION, THE UNIT BID PRICE SHALL INCLUDE FOR MATERIALS AND INSTALLATION OF THE REINFORCING STEEL DOWELS.

THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY (SHEET NO. 4) - 80 EA.

ITEM 511- CONCRETE FOR STRUCTURES

THE CONCRETE SHALL BE CLASS "C". THIS WORK SHALL BE DONE IN ACCORDANCE WITH ODOT ITEM 511. IN ADDITION, THIS UNIT BID PRICE SHALL INCLUDE MATERIALS AND INSTALLATION OF THE #3 HORIZONTAL REINFORCING STEEL.

THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY (SHEET NO. 4) - 10 CU. YD.

CALCULATED	CREATED	WALL RECONSTRUCTION GENERAL NOTES	NINTH STREET	3 / 4	27 29