

ITEM	FROM SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION
	2	8	9	16	23	25	26	27								
																*** ROADWAY ***
201							1					201		1	LUMP	CLEARING AND GRUBBING
202			3633									202		3633	SQ YD	PAVEMENT REMOVED
202			647									202		647	SQ YD	WEARING COURSE REMOVED
202			260									202		260	LIN FT	CURB REMOVED
202			150									202		150	LIN FT	WALL REMOVED
202			1439									202		1439	SQ YD	PAVEMENT BROKEN UP AND LEFT IN PLACE
202			8									202		8	EACH	CATCH BASIN OR INLET REMOVED
202			1									202		1	EACH	MANHOLE REMOVED
202			125									202		125	LIN FT	PIPE REMOVED
203		8517										203		8517	SQ YD	SUBGRADE COMPACTION
203					5290							203		5290	CU YD	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
203					5778							203		5778	CU YD	EMBANKMENT
203	1											203		1	HR	PROOF ROLLING
510								80				510		80	EACH	DOWEL HOLES
511								10				511		10	CU YD	CONCRETE FOR STRUCTURES
606			6.25									606		6.25	LIN FT	GUARDRAIL, TYPE 5
606			2									606		2	EACH	ANCHOR ASSEMBLY, TYPE B
608				9								608		9	EACH	CURB RAMP, ODOT TYPE 2
608			1400									608		1400	LIN FT	CONCRETE WALK (5' WIDTH)
616	5											616		5	M. GAL	WATER FOR DUST CONTROL
616	0.5											616		0.5	TONS	CALCIUM CHORIDE
SPECIAL						100						SPECIAL		100	SQ YD	CONCRETE REPAIR (2" DEPTH OR GREATER)
SPECIAL						50						SPECIAL		50	SQ YD	CONCRETE REPAIR (2" DEPTH OR LESS)
SPECIAL							100					SPECIAL		100	LIN FT	SAWCUT JOINT
																*** EROSION CONTROL ***
207	1500											207		1500	LIN FT	FILTER FABRIC FENCE
207	136											207		136	EACH	STRAW OR HAY BALES
601			2.5									601		2.5	CY YD	ROCK CHANNEL PROTECTION, TYPE D, W/O FILTER FABRIC (3' WIDTH)
601			292									601		292	LIN FT	PAVED GUTTER, TYPE 4, (3' WIDTH)
659	15300											659		15300	SQ YD	SEEDING AND MULCHING
659	765											659		765	SQ YD	REPAIR SEEDING AND MULCHING
659	0.03											659		0.03	M GAL	WATER
																*** DRAINAGE ***
603			339									603		339	LIN FT	12" CONDUIT, TYPE B (707.41)
603			77									603		77	LIN FT	12" CONDUIT, TYPE C (707.41)
603			276									603		276	LIN FT	8" CONDUIT, TYPE B (707.44)
603			14									603		14	LIN FT	4" CONDUIT, TYPE B (707.41)
604			7									604		7	EACH	MANHOLE, CATCH BASIN OR INLET RECONSTRUCTED TO GRADE
604			11									604		11	EACH	CATCH BASIN ODOT NO. 3
604			2									604		2	EACH	MANHOLE ODOT NO. 3
604			1									604		1	EACH	CATCH BASIN ODOT NO. 4
605							550					605		550	LIN FT	SHALLOW PIPE UNDERDRAINS, WITH FILTER FABRIC
SPECIAL			85									SPECIAL		85	LIN FT	PLUG AND FILL EXISTING CONDUIT
SPECIAL			2									SPECIAL		2	LIN FT	PRECAST UNDERDRAIN OUTLETS
SPECIAL			297									SPECIAL		297	LIN FT	36" CONDUIT, TYPE B (PIPE LINING); (707.43)
																*** PAVEMENT ***
301		1063										301		1063	CU YD	BITUMINOUS AGGREGATE BASE, AC-20
304		1419										304		1419	CU YD	AGGREGATE BASE
402		372										402		372	CU YD	ASPHALT CONCRETE, AC-20
404		289										404		289	CU YD	ASPHALT CONCRETE, AC-20
407		65										407		65	GALLON	TACK COAT
408		3082										408		3082	GALLON	BITUMINOUS PRIME COAT
609		2919										609		2919	LIN FT	CONCRETE CURB, TYPE 2 (8" THICKNESS)
																*** LIGHTING ***
625			4									625		4	EACH	PULL BOX, CONCRETE 13" X 18"
625			2733									625		2733	LIN FT	3" CONDUIT, 713.07
																*** TRAFFIC CONTROL ***
642				2328								642		2328	LIN FT	LANE LINE, DASHED
642				1082								642		1082	LIN FT	CENTER LINE, DOUBLE SOLID
642				414								642		414	LIN FT	CHANNELIZING LINE, WHITE
642				351								642		351	LIN FT	ISLAND MARKING, YELLOW
642				100								642		100	LIN FT	STOP LINE
642				14								642		14	EACH	LANE ARROW
642				5								642		5	EACH	WORD "ONLY" ON PAVEMENT, 96"
642				502								642		502	LIN FT	CROSSWALK LINES, WHITE
614												614			LUMP	MAINTAINING TRAFFIC
619												619			LUMP	FIELD OFFICE, TYPE B
623												623			LUMP	CONSTRUCTION LAYOUT STAKES
624												624			LUMP	MOBILIZATION

CALCULATED	CHECKED
GENERAL SUMMARY	
NINTH STREET	
4	29