

ROADWAY DRAINAGE (D)

Item No.	Station	Side	Pipe for Storm Sewers under Pav't Lin. Ft.	Outlet Pipe for Storm Sewers 12" 25' Lin. Ft.	Pipe Specials Bends Units	Riprap Sq. Yds.
1-D	1028+50	Rt.	26	56	2	
2-D	1031+00	Rt.	26	46	2	
3-D	1033+48	Rt.	26	26		7
4-D	1036+00	Rt.	26	24		6
Totals			104	152	4	13

CATCH BASINS (I)

Item No.	Station	Side	Catch Basins No. 3 Modified Units
1-I	1028+50	Lt.	1
2-I	1031+00	Lt.	1
3-I	1033+48	Lt.	1
4-I	1036+00	Lt.	1
Total			4

PAVEMENT REMOVAL (P)

Item No.	Station	From	To	Length	Width	6" Sq. Yds.	8" Sq. Yds.
1-P	1027+00	1028+45	150'	22	366.7		
2-P	1028+45	1032+25	38.5	16'	684.4		
Total						366.7	684.4

CONCRETE CURB & GUTTER (C)

Item No.	Station	Side	Type 4 Integral Conc. Curb & Gutter Lin. Ft.
1-C	1027+00	Lt.	636.4
2-C	1033+98.6	Lt.	396.4
Total			1032.8

TREE PROTECTION

Item No.	Station	Rt. or Lt.	Rip Rap for Tree Protection Sq. Yds.	Agar for Root Protection Cu. Yds.
1-T	1030+77	Rt.	9	13
Total			9	13

DRIVES & APPROACHES (A)

Item No.	Station	Side	Details on Sheet No.
1-A	1030+00	Rt.	32
2-A	1033+75	Lt.	33

GUARD RAIL (G)

Item No.	Station	Side	Guard Rail I-15.05 Lin. Ft.	Guard Rail I-15.05 Lin. Ft.
1-G	1027+00	Rt.	266	
2-G	1030+20	Rt.	782.6	
3-G	1032+25	Lt.		25
Totals			1048.6	25

STRUCTURES 20' SPAN & UNDER

Struct. No.	Station	Description	Details on Sheet No.
2	Rt. 1030+00 Typ. Road Sta. 1+25	16'x12'x69' Large Box Culvert	145
3	1033+25	48'x124'0" Standard Pipe Culvert	146
1	1027+83	Remove exist. 14'x38' C.I. Pipe Culvert incl. Halwalls	162

