

MUSKINGUM COUNTY MUS-146-0.15

ROADWAY QUANTITIES

Reference Number	Station to Station	Side	I-15	I-15	I-18	I-35	E-8	E-12	Special	Special
			Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yds.	Lin.Ft.	Lin.Ft.	Lump
1-R	10+00 to 10+25	Rt.	25							
2-R	10+00 to 10+87.5	Lt.		87.5						
3-R	10+00 to 11+66	Rt.					300			
4-R	12+00	Rt.			15.80	6.3		16		
5-R	12+00	Lt.			13.20					
6-R	17+32 to 20+00	Rt.			287.50					
7-R	16+50 to 20+00	Lt.			350.00					
8-R	18+63	Rt.							136	Lump
9-R	18+63 to 20+00	Rt.								Lump
TOTALS			25	725	29.00	6.3	300	16	136	Lump

DRAINAGE QUANTITIES

Reference Number	Station to Station	Side	I-1	I-4	I-4	I-5	I-10	I-14	I-10
			Lin.Ft.	Lin.Ft.	Lin.Ft.	Each	Cu.Yds.	Lin.Ft.	Sq.Yds.
1-D	10+00 to 10+18	Lt.						12	
2-D	10+00 to 10+50	Rt.						33	
3-D	11+00 to 17+26	Lt.		626	10	1			
4-D	11+00 to 17+69	Rt.		679	10	1			
5-D	11+25 to 11+66	Rt.						27	
6-D	12+00	Lt.	34						
7-D	12+00	Rt.	42						
8-D	12+02 to 12+85	Rt.					28	346	See Note on Sheet #14
9-D	12+15 to 18+28	Lt.						409	
10-D	18+43 to 19+55	Lt.						75	
11-D	17+05 to 18+08.50	Rt.					13		
12-D	19+55 to 20+00	Lt.					45	30	See Note on Sheet #14
13-D	19+53 to 20+00	Rt.		55	10	1			
14-D	19+53 to 20+00	Lt.		47	10	1			
15-D	19+58 to 20+00	Lt.							
②	See Sheet No. 29								
③	See Sheet No. 30								
TOTALS			76	1407	40	4	13	73	932

REVISION	DATE	DESCRIPTION	BY
U. S. ARMY ENGINEER DISTRICT, HUNTINGTON CORPS OF ENGINEERS HUNTINGTON, W. VA.			
DRAWN BY: <i>E.S.B.</i>		LICKING RIVER DILLON RESERVOIR PROJECT RELOCATION OF OHIO STATE ROUTE NO. 146 (Section I)	
TRACED BY: <i>E.S.B.</i>		ELMER S. BARRETT ASSOCIATES	
CHECKED BY: <i>E.S.B.</i>		APPROVED: <i>E.S.B.</i> DATE: June, 1959	
SUBMITTED BY: <i>E.S.B.</i>		CHIEF ENGINEER	
RECOMMENDED: <i>E.S.B.</i>		ELMER S. BARRETT ASSOCIATES CONSULTING ENGINEERS CHILLICOTHE, OHIO	
SCALE: 1" = 40'		SPEC. NO. DRAWING NUMBER 0271-UD5-68/17 SHEET 17 OF 36	

