

Stru No.	Station	Proposed			Details on Sheet
		Type	Size	Length	
G	304+68	Pipe	48"	126'	216

Mark	Station		Side	Stabilized Berm Sq. Yds
	From	To		
1-B	304+00	315+00	Lt	483
2-B	304+00	315+00	Rt	483
Total				978

Mark	Station	Side	Type	Details on Sheet

Mark	Station		Side	L-10 Sodding Sq.Yds.	I-14 Paved Gutter Lin Ft	I-10 Dumped Rock Chan.Protect
	From	To		Type 1	Type 1	Cu. Yds.
					As Per Plan 510	
1-D	305+08	310+10	Lt.			
2-D	308+50	308+80	Rt.			12
3-D	308+80	313+00	Rt.		423	
4-D	310+10	312+50	Lt.	241		
5-D	312+50	313+10	Lt.			24
6-D	313+00	315+00	Rt.	133		
7-D	313+10	315+00	Lt.	190		
	Total			564	423	510
						36

Mark	Station		Side	I-15 Guardrail S.B. (deep) Lin. Ft.	
	From	To			
1-G	304+33	311+45 [±]	Rt.	712 ^s	
2-G	304+75	306+50	Lt.	175	
	Total			887 ^s	

Mark	Station		Side	I-4 6" Pipe Underdrain Lin.Ft	I-4 8" Outlet Pipe Lin.Ft	I-5 6"x 45° Pipe Spc. Each
	From	To				
I-U	313+50	315+00	Rt.	146'	10	1
Totals				146'	10	1

