

PER. 75-26.57
MUS. 75-0.00

B STABILIZED BERMS

Mark	Station		Side	Stabilized Berm Sq Yds
	From	To		
1-B	315+00	326+00	Lt	489
2-B	315+00	326+00	Rt	489
Total				978

A DRIVES AND APPROACHES

Mark	Station	Side	Type	Details on Sheet

D DITCHES

Mark	Station		Side	L-10 Sodding Sq Yds		I-10 Dumped Rock Chan Protect Cu Yds
	From	To		Type 1	Type 2	
1-D	315+00	317+00	Lt	200		
2-D	315+00	317+00	Rt	133		
3-D	320+20	322+00	Lt	110	17	
4-D	325+86	326+05	Lt			9
Total				443	17	9

U PIPE UNDERDRAINS

Mark	Station		Side	I-4 6" Pipe Underdrain Lin Ft.	I-4 8" Outlet Pipe Lin. Ft.	I-5 6" x 45° Pipe Spe. Each
	From	To				
1-U	315+00	317+00	Rt	200		
Total				200		

