

PER. 75-26.57
MUS. 75-0.00

STRUCTURES 20' SPAN & UNDER

Stru No	Station	Proposed			Details on Sheet
		Type	Size	Length	
8	351+05	Pipe	54"	256'	218
9	353+05	Pipe	24"	166'	219

(B) STABILIZED BERMS

Mark	Station		Side	Stabilized Berm Sq Yds
	From	To		
1-B	348+00	353+00	Lt	489
2-B	348+00	353+00	Rt	489
Total				978

(D) DITCHES

Mark	Station		Side	L-10 Sodding Sq Yds		I-14 Paved Gutter Type 1 Lin. Ft.	I-10 Dumped Rock Chan. Protect Cu. Yds
	From	To		Type 1	Type 2		
1-D	348+00	348+25	Lt	17			
2-D	348+00	349+00	Rt				36
3-D	348+25	349+75	Lt				68
4-D	349+00	350+76	Rt	120			7
5-D	349+75	351+42	Lt	116			
6-D	350+86	352+00	Rt				53
7-D	351+42	352+50	Lt				50
8-D	352+00	353+75	Rt	122			
9-D	352+50	355+50	Lt	133	67		
10-D	353+75	353+00	Lt		20		
	Total			508	87		216

(G) GUARD RAIL

Mark	Station		Side	I-15 Guard Rail S.B. (deep) Lin. Ft.
	From	To		
1-G	348+00	352+75	Lt	475
2-G	348+00	352+75	Rt	475
3-G	353+25	353+00	Rt	75
Total				1025

