

PER. 75-26.57
MUS. 75-0.00

B. STABILIZED BERMS

Mark	Station		Side	Stabilized Berm Sq. Yds.
	From	To		
1-B	370+00	381+00	Lt.	453
2-B	370+00	381+00	Rt.	483
Total				936

D. DITCHES

Mark	Station		Side	L-10 Sodding Sq. Yds.		I-14 Paved Gutter Lin. Ft.		I-10 Dumped Rock Chan. Protect. Cu. Yds.	
	From	To		Type 1	Type 2	Type 1	Type 2	Type 1	Type 2
1-D	370+00	374+50	Lt.	450					
2-D	372+50	373+00	Lt.	436					
3-D	373+50	373+35	Rt.			38			
4-D	376+00	377+00	Lt.	100					
5-D	377+00	379+50	Lt.					250	
6-D	379+00	381+00	Lt.						87
7-D	379+00	380+00	Rt.			74			
8-D	380+00	381+00	Lt.			105			
Total				986	112	105	250	87	

G. GUARD RAIL

Mark	Station		Side	I-15 Guard Rail S.B. (deep) Lin. Ft.
	From	To		
1-G	373+70	375+70	Rt.	200
2-G	379+50	381+00	Rt.	150
3-G	379+75	381+00	Lt.	125
Total				475

