

PER. 75-26.57
MUS. 75-0.00

STRUCTURES 20' SPAN & UNDER

Stru. No.	Station	Proposed			Details on Sheet
		Type	Size	Length	
16	442+60	Pipe	60"	208'	227
17	446+00	Pipe	48"	126'	228

(B) STABILIZED BERMS

Mark	Station		Side	Stabilized Berm Sq. Yds.
	From	To		
1-B	436+00	438+73	Lt.	124
2-B	436+00	438+70	Rt.	122
3-B	439+38	447+00	Lt.	343
4-B	439+27	447+00	Rt.	347
Total				936

(A) DRIVES AND APPROACHES

Mark	Station	Side	Type	Details on Sheet
1-A	439+00	Rt.	Co. Rd. 47	202
2-A	439+00	Lt.	Appr. Rd.	202
3-A	8+35	Lt. Appr.	Service Rd.	208

(G) GUARD RAIL

Mark	Station		Side	I-15 Guard Rail S.B. (deep) Lin. Ft.
	From	To		
1-G	9+00 Appr.	447+00	Lt.	800
2-G	439+75	447+00	Rt.	725
Total				1575

(X) REMOVALS

Mark	Station		I-15 Guard Rail Rem. of Ex. Structure Lin. Ft.	S-22 Rem. of Portion of Ex. Pav't Structures Lump	E-8 Rem. & Disp. of Ex. Pav't Structures Sq. Yds.	S-24 Rem. of Ex. Structures Lump
	From	To				
1-X	441+64	445+82	428	Lump		Lump
2-X	442+39					
3-X	445+60			Lump		
4-X	445+63			Lump		
5-X	445+50			Lump		
6-X	441+27	444+60			650	
7-X	445+13	445+45	32			
Total			460		650	

