

GENERAL SUMMARY TABLE

Calc. By J.C.N. 10-22-73
Ckd By P.D.H. 10-22-73

4-1

MARR **KNAPP** **CRAWFIS**
REGISTERED ARCHITECTS, INC.
NEW PHILADELPHIA
MANSFIELD OHIO OHIO

FROM QUANTITY CALCULATIONS	FROM SHEET NO.			GRAND TOTAL	UNIT	ITEM	DESCRIPTION
	3-A	5-A	6-A				
							ROADWAY
			136	136	Lump Sum	201	Clearing and Grubbing
25,116				25,116	Lin. Ft.	202	Pipe Removed
34,305			24	34,329	Cu. Yd.	203	Embankment
7616				7616	Cu. Yd.	203	Excavation, Not Including Embankment Construction
					Sq. Yd.	203	Subgrade Compaction
	25			25	Cu. Yd.	404	Asphalt Concrete or Approved Bituminous Pre-mixed Surface Course For Maintaining Traffic
60				60	Cu. Yd.	410	Traffic Compacted Surface Type A or B
190				190	Cu. Yd.	410	Traffic Compacted Surface Type C
			350	350	Lin. Ft.	606	Guard Rail, Standard Type 4
			4	4	Each	606	Anchor Assembly
5				5	Tons	616	Calcium Chloride
							PAVEMENT
1536		48	35	1619	Cu. Yd.	304	Aggregate Base
810				810	Cu. Yd.	310	Subbase
							DRAINAGE
			106	106	Cu. Yd.	602	Concrete Masonry
			92	92	Lin. Ft.	603	27" Conduit, Type A 707.05
		82	44	126	Lin. Ft.	603	12" Conduit, Type A
			1	1	Each	604	Manhole Reconstructed to Grade
676				676	Lin. Ft.	605	Aggregate Drains
							EROSION CONTROL
			67	67	Cu. Yd.	601	Rock Channel Protection, Type B
			12	12	Sq. Yd.	601	Riprap, Using 6" Reinforced Concrete Slab
23,064				23,064	Sq. Yd.	659	Seeding and Mulching
2.24	0.29			2.53	Ton	659	Commercial Fertilizer (12-12-12)
11.21				11.21	Ton	659	Agricultural Liming
		710	1126	1836	Sq. Yd.	667	Seeding and Jute Matting
	6450			6450	Sq. Yd.	207	Temporary Seeding and Mulching
	680			680	Lin. Ft.	207	Temporary Slope Drains
	25			25	Cu. Yd.	207	Temporary Benches, Dikes, Dams, and Sediment Basins
	58			58	M. Sq. Ft.	207	Mowing
	Lump Sum				Lump Sum	614	Maintaining Traffic
					Lump Sum	623	Construction Layout Stakes

GENERAL SUMMARY TABLE

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

REVISIONS	SCALE
-----------	-------

AS NOTED	OF
----------	----

