

TOWNSHIP 12 N. - RANGE 13 W.
U.S. MILITARY LANDS

Diagram illustrating the cross-section of a concrete wall. The wall is 36" high and 1'-6" wide. A 1/2" steel rod is embedded in the concrete. The upper 6" of the wall shall be formed. The wall is labeled CLASS C CONCRETE.

② REFERENCE MONUMENT

UNDERWOOD ST.
MOUNTAIN SQ.

STA. 14+03.12, 3.37' LT. UNDERWOOD ST. =
STA. 889+00.00 UNDERWOOD ST. (MUS-60-16.88)

DEFLECTION POINT
STA. 890+25.66
 $\Delta = 3^{\circ}58'15''$ RT.

REF. MON. FND.
891+67.32. 45' LT

STA. 891+28.34 UNDERWOOD ST.
= C MARKET STREET

STA. 653+18.55 GREENWOOD AVE (U.S. 22)
= STA. 41+66.90 FOUNTAIN SQ.

NOTE

CENTERLINE MONUMENTS AND CENTERLINE REFERENCE MONUMENTS ARE SHOWN ON STANDARD CONSTRUCTION DRAWING MC-1 (REV. 6-13-69) OF THE OHIO DEPARTMENT OF TRANSPORTATION. THE PLACING OF THE MONUMENTS SHALL BE UNDER THE DIRECTION OF A REGISTERED SURVEYOR AND ARE TO BE SET, AS SHOWN BY THE HIGHWAY CONTRACTOR AT THE TIME OF CONSTRUCTION. ANY ALTERATIONS, WITH PRIOR APPROVAL OF THE OHIO DEPARTMENT OF TRANSPORTATION, SHALL BE NOTED AND O.D.O.T. SHALL BE NOTIFIED OF THE NEW LOCATIONS.

RECEIVED _____
RECORDED _____
BOOK _____
PAGE _____

STATIONING

ALL STATIONING IS BASED ON THE
CENTERLINE OF SURVEY UNLESS
OTHERWISE SPECIFIED.

BEARINGS

ALL BEARINGS ARE BASED UPON AN ASSUMED MERIDIAN AND ARE USED ONLY FOR THE PURPOSE OF ANGULAR MEASUREMENTS.

I HEREBY CERTIFY THAT THIS IS A TRUE
DELINEATION OF A SURVEY MADE FOR THE OHIO
DEPARTMENT OF TRANSPORTATION, IN 1991.

BY Regn M. Smith
REGISTERED SURVEYOR NO. 56899 DATE 20 OCT 95

SURVEYOR'S SEAL

MONUMENTS TO BE SET DURING CONSTRUCTION				
STATION	DIST. FROM C OF SURVEY		C MONUMENT ASSEMBLY, AS PER PLAN	RIGHT OF WAY MONUMENT, AS PER PLAN
	LEFT	RIGHT		
STA. 649+00 U.S. 22	ON C	ON C	1	
STA. 651+70.54 U.S. 22	ON C	ON C	1	
STA. 653+17.96 U.S. 22	ON C	ON C	1	
STA. 653+77.91 U.S. 22	ON C	ON C	1	
STA. 13+37.34 UNDERWOOD ST. = STA. 40+00 FOUNTAIN SQ.	ON C	ON C	1	

PID NO. 6465

STATE PROJECT NO. 051850

CENTERLINE SURVEY PLAT

MUS-22-12.28

1

31
36