

GREENWOOD AVENUE ESTIMATED QUANTITIES

REF. NO.	STATION TO STATION	SIDE	202 Curb Removed	202 CB or Inlet Removed	202 Walk Removed	603 12" Conduit Type C	603 6" Conduit Type F Non-Perf	603 12" Conduit Type B	603 18" Conduit Type B	604 Catch Basin No. 2-2A	604 Catch Basin No. 3A	604 Manhole No. 3	605 6" Shallow Under- drain	608 4" Conc. Walks	612 9" Conc. Traffic Island	609 Curb, Type 6
UNITS			Lin.ft.	Each	Sq. ft.	Lin.ft.	Lin.ft.	Lin.ft.	Lin.ft.	Each	Each	Each	Lin.ft.	Sq. ft.	Sq.Yd.	Lin.ft.
R3	650+00 Rt. Greenwood to 5+74 Rt. Silliman	Rt.	305													
R4	5+74 Lt. Silliman to 653+88 Rt. Greenwood	Rt.	114													
R7	649+78 Rt. Greenwood to 5+74 Rt. Silliman	Rt.			1657											
R9	5+74 Lt. Silliman to 652+26 Rt. Greenwood	Rt.			1261											
R10	652+55 to 653+67	Rt.			644											
R12	653+05 to 653+50	Lt.			311											
R15	651+05	Rt.		1												
SW10	653+00 to 653+50	Lt.												516		
SW11	653+31 to 653+67	Rt.												303		
SW12	652+56 to 653+12	Rt.												295		
SW13	5+74 Lt. Silliman to 652+24 Rt. Greenwood	Rt.												947		
SW14	649+78 Rt. Greenwood to 5+74 Rt. Silliman	Rt.												1657		
D20	651+14 to 651+09	Rt.						14			1					
D21	651+09 Rt. Greenwood to 5+52 Lt. Silliman	Rt.						14		1						
D25	652+11 to 651+09	Rt.				92										
D17	653+60 to 653+60	Lt.						7			1					
D18	653+60 Lt. Greenwood to 40+59 Lt. Fountain Sq.	Lt.							148			1				
D19	653+60 Rt. to 653+60 Lt.	Lt.						30			1					
D34	649+84 to 649+94	Rt.					10									
D35	649+94 to 650+58	Rt.											69.98			
D36	651+16 to 652+26	Rt.					10									
D37	652+26 to 653+00	Rt.											159.98			
D38	651+01 to 651+12	Rt.											15.36			
D39	650+98 to 651+01	Rt.					10									
C9	5+74 Lt. Silliman to 653+78 Rt. Greenwood	Rt.														301
C10	11+00 Rt. Greenwood to 5+74 Rt. Silliman	Rt.														124
C12	651+12 to 652+55	Lt.														142
T1	Greenwood	Lt.													504	
Totals to General Summary			419	1	3873	92	30	65	148	1	3	1	245	3718	504	567

UNDERWOOD STREET ESTIMATED QUANTITIES

REF. NO.	STATION TO STATION	SIDE	202 Curb Removed	202 2" Poly- ethylene Service Ditches	202 Guard Posts Removed	202 Walk Removed	603 6" Conduit Type F Non-Perf	603 12" Conduit Type B	603 24" Conduit Type B	604 Catch Basin No. 3A	604 Manhole No. 3	605 6" Shallow Under- drain	608 Curb Ramp Type 2	608 4" Conc. Walk	609 Curb, Type 6
UNITS			Lin.ft.	Lin.ft.	Each	Sq. ft.	Lin.ft.	Lin.ft.	Each	Each	Each	Lin.ft.	Each	Sq. ft.	Lin.ft.
R1	11+00 Lt. Underwood to 39+56 Rt. Fountain Sq.		298												
R2	39+56 Lt. Fountain Sq. to 14+00 Lt. Underwood	Lt.	144												
R5	14+54 Rt. Underwood to 653+88 Lt. Greenwood		306												
R6	10+85 Lt. Underwood to 39+56 Rt. Fountain Sq.					3018									
R8	39+56 Lt. Fountain Sq. to 14+54 Lt. Underwood	Lt.				748									
R17	12+36	Lt.			1										
R18	12+42	Rt.			1										
R20	12+09	Lt.				33									
R21	12+14	Rt.				28									
SW5	10+85 to 11+28	Lt.												380	
SW6	11+42 Lt. Underwood to 39+56 Rt. Fountain Sq.	Lt.												1710	
SW7	39+56 Lt. Fountain Sq. to 13+74 Lt. Underwood	Lt.												247	
SW8	13+74 to 14+65	Lt.												618	
CR5	13+16	Lt.											1		
D12	14+00 to 14+00	Lt.						7		1					
D13	14+00 to 890+66	Lt.									1				
D26	14+67 to 14+00	Lt.						66							
D27	14+15	Lt.							16		1				
D40	10+88 to 10+98	Lt.					10								
D41	10+98 to 12+25	Lt.											129.51		
D42	12+26 to 13+14	Lt.											87.86		
D43	13+14 to 13+23	Lt.					10								
D44	13+50 to 13+88	Lt.											38.44		
D45	13+88 to 13+98	Lt.					10								
D46	14+02 to 14+55	Lt.											51.69		
D47	14+55 to 14+65	Lt.					10								
W1	14+40 to 13+30	Rt.		190											
C6	11+00 Lt. Underwood to 39+56 Rt. Fountain Sq.	Lt.													236
C7	39+56 Lt. Fountain Sq. to 14+70 Lt. Underwood	Lt.													145
C8	14+59 Rt. Underwood to 653+78 Lt. Greenwood	Rt.													290
C13	12+11 to 13+18	Rt.													113
Totals to General Summary			748	190	2	3827	40	73	16	2	2	308	1	2955	784

FOUNTAIN SQUARE ESTIMATED QUANTITIES

REF. NO.	STATION TO STATION	SIDE	202 CB or Inlet Removed	202 Walk Removed	603 6" Conduit Type F Non-Perf	603 12" Conduit Type B	603 18" Conduit Type B	604 Catch Basin No. 3A	604 Manhole No. 3	605 6" Shallow Under- drain	608 4" Conc. Walk	608 Curb Ramp Type 2	609 Curb, Type 6
UNITS			Each	Sq. ft.	Lin.ft.	Lin.ft.	Lin.ft.	Each	Each	Lin.ft.	Sq. ft.	Each	Lin.ft.
R11	14+59 Rt. Underwood to 41+35 Lt. Fountain Sq.			1186									
R16	40+27	Lt.	1										
R19	41+33	Lt.	1										
SW9	14+59 Rt. Underwood to 41+35 Lt. Fountain Sq.											1499	
CR6	39+74	Lt.											1
C11	40+19 to 41+06	Rt.											87
D11	39+68 Rt. Fountain Sq. to 14+00 Lt. Underwood					76		1					
D14	40+59 Lt. Fountain Sq. to 14+00 Lt. Underwood	Lt.					86		1				
D15	40+59 to 40+59	Lt.			7								
D16	41+25 to 40+59	Lt.			66			1					
D48	653+60 Lt. Greenwood to 41+37 Lt. Fountain Sq.	Lt.								66.59			
D49	41+27 to 41+37	Lt.			10								
D50	40+71 to 41+22	Lt.								51.47			
D51	40+61 to 40+71	Lt.			10								
Totals to General Summary			2	1186	20	149	86	3	1	118	1499	1	87

SILLIMAN AVENUE ESTIMATED QUANTITIES

REF. NO.	STATION TO STATION	SIDE	202 CB or Inlet Removed	603 6" Conduit Type F Non-Perf	603 12" Conduit Type B	603 18" Conduit Type B	604 Catch Basin No. 3A	604 Manhole No. 3	605 6" Shallow Under- drain	608 Curb Ramp Type 2
UNITS			Each	Lin.ft.	Lin.ft.	Lin.ft.	Each	Each	Lin.ft.	Each
R13	5+29	Rt.	1							
R14	5+47	Lt.	1							
CR7	5+40	Lt.								1
CR8	5+21	Rt.								1
D22	5+52 Lt. to 5+23 Rt.				38		1			
D23	5+23 Rt. Silliman to 649+82 Rt. Greenwood	Rt.				80		1		
D24	5+28 to 5+23	Rt.			7					
D52	5+30 to 5+40	Rt.		10						
D53	5+40 to 5+74	Rt.							34	
D54	5+53 to 5+63	Lt.		10						
D55	5+63 to 5+74	Lt.							11	
Totals to General Summary			2	20	45	80	2	1	45	2

ESTIMATED QUANTITIES

MUS-22-12.28

9
35