

FED. AID DIST. NO.	STATE	U.S.P.W. PROJ.	FISCAL YEAR	9
10	OHIO	N.R.M. 6330	1934	9

**S.H.(I.C.H.) 1 SEC. ZANESVILLE (PT.)
MUSKINGUM COUNTY**

(LEFT SIDE)			CONCRETE		SIDEWALK		(RIGHT SIDE)	
LOCATION	DIMENSIONS	Sq. Ft.	LOCATION	DIMENSIONS	Sq. Ft.			
Sta. 0+15.85 ~Sta. 1+73.65	183.50' x 4'	733.00	Sta. 0+15.85 to Sta. 1+70.83	186.73' x 0.50'	93.37			
N.W. Ret. First St. & Main	18' x 4'	72.00	S.W. Ret. First & Main	18' x 4'	72.00			
N.E. " " " "	18' x 4'	72.00	S.E. " " " "	18' x 4'	72.00			
Basin at N.E. Cor. First & Main	11' x 4'	44.00	Basin at S.E. Ret. First & Main	11' x 4'	44.00			
Sta. 2+46.10 to Sta. 3+71.23	125.83' x 4'	503.32	Sta. 2+52.03 ~ Sta. 3+69.50	117.47' x 0.50'	58.74			
N.W. Ret. of Alley E. of First St.	15' x 2'	30.00	S.W. Ret. of Alley E. of First St.	15' x 2'	30.00			
N.E. " " " " "	15' x 2'	30.00	Sta. 3+23.50 ~ Sta. 5+48.75	155.25' x 0.50'	77.63			
Sta. 3+25.03 ~Sta. 5+33.55	138.52' x 4'	554.08	Basin at S.E. Cor. 2 nd St.	16.5' x 4'	66.00			
Basin at N.E. Cor. Second St.	16.5' x 4'	66.00	Sta. 6+02.90 ~ Sta. 7+28.25	125.35' x 0.50'	62.68			
Sta. 6+02.25 ~ Sta. 7+28.55	126.3' x 0.50'	63.15	S.W. Ret. Beech Alley	15' x 2'	30.00			
N.W. Ret. on Beech Alley	15' x 2'	30.00	S.E. " " " "	15' x 2'	30.00			
N.E. " " " " "	15' x 2'	30.00	Sta. 7+50.68 ~ Sta. 8+79.13	128.50' x 4'	514.00			
Sta. 7+51.22 ~ Sta. 8+79.15	127.93' x 4'	511.72	S.W. Ret. Third & Main	18' x 4'	72.00			
N.E. Ret. of Third & Main	3.1416 x (12) ² ÷ 4	113.09	S.E. " " " "	18' x 4'	72.00			
Special Inlet at Third & Main	11' x 4'	44.00	Basin at S.E. Cor. 3 rd & Main	11' x 4'	44.00			
Basin at N.E. Cor. Third & Main	11' x 4'	44.00	Sta. 9+56.38 ~ Sta. 10+76.70	119.72' x 4'	478.88			
Sta. 9+55.90 ~ Sta. 10+75.40	119.5' x 4'	478.00	S.W. Ret. of Potter Alley	15' x 2'	30.00			
N.W. Ret. of Potter Alley	15' x 2'	30.00	S.E. " " " "	15' x 2'	30.00			
N.E. " " " " "	15' x 2'	30.00	Sta. 10+99.10 to Sta. 12+30	130.9' x 4'	533.60			
Sta. 10+98.68 ~ Sta. 12+29.05	130.37' x 4'	521.48	S.W. Ret. of Fourth & Main	18' x 4'	72.00			
N.W. Ret. of Fourth St.	18' x 4'	72.00	S.E. " " " "	18' x 4'	72.00			
Basin at N.W. Ret. of Fourth St.	11' x 4'	44.00	Basin at S.E. Cor. Fourth & Main	11' x 4'	44.00			
N.E. Ret. of Fourth St.	3.1416 x (12) ² ÷ 4	113.09	Sta. 13+04.18 ~ Sta. 14+29.33	125.15' x 0.50'	62.58			
Special Inlet Fourth & Main	11' x 4'	44.00	S.W. Ret. of Court Alley	15' x 2'	30.00			
Basin at N.E. Cor. Fourth & Main	11' x 4'	44.00	S.E. " " " "	15' x 2'	30.00			
Sta. 13+06.92 ~ Sta. 14+23.40	121.48' x 0.50'	60.74	Sta. 14+49.85 ~ Sta. 15+89.80	139.95' x 0.50'	69.98			
N.W. Ret. of Court Alley	15' x 2'	30.00	S.W. Ret. of Fifth St.	18' x 4'	72.00			
N.E. " " " " "	15' x 2'	30.00	S.E. " " " "	18' x 4'	72.00			
Sta. 14+51.15 ~ Sta. 15+89.22	138.07' x 0.50'	69.03	Basin at S.E. Ret. of Fifth St.	16.5' x 4'	66.00			
N.W. Ret. of Fifth & Main	18' x 4'	72.00	Sta. 16+69.40 ~ Sta. 17+91.21	121.80' x 0.50'	60.90			
N.E. " " " " "	18' x 4'	72.00	S.W. Ret. of Sewer Alley	15' x 2'	30.00			
Basin at N.E. Ret. Fifth & Main	11' x 4'	44.00	S.E. " " " "	15' x 2'	30.00			
Sta. 16+64.27 ~ Sta. 17+92	127.73' x 0.50'	63.86	Sta. 18+14.65 ~ Sta. 19+51.20	136.55' x 0.50'	68.28			
N.W. Ret. of Sewer Alley	15' x 2'	30.00	Sta. 20+22.85 ~ Sta. 21+48.45	125.60' x 4'	502.40			
N.E. " " " " "	15' x 2'	30.00	S.W. Ret. of Cypress Alley	15' x 2'	30.00			
Sta. 18+10.40 ~ Sta. 19+50.65	137.25' x 0.50'	68.62	S.E. " " " "	15' x 2'	30.00			
N.E. Ret. of Sixth St.	3.1416 x (12) ² ÷ 4	113.09	Sta. 21+70.80 ~ Sta. 23+03.92	133.12' x 4'	532.48			
Special Inlet Sixth & Main	11' x 4'	44.00	S.W. Ret. of Seventh St.	18' x 4'	72.00			
Basin N.E. Cor. Sixth & Main	11' x 4'	44.00	Basin at S.W. Ret. 7 th & Main	11' x 4'	44.00			
Sta. 20+26.25 ~ Sta. 21+48.12	121.87' x 4'	497.48	S.E. Ret. of Seventh & Main	3.1416 x (12) ² ÷ 4	113.09			
N.W. Ret. of Cypress Alley	15' x 2'	30.00	Special Inlet at 7 th & Main	11' x 4'	44.00			
N.E. " " " " "	15' x 2'	30.00	Basin at S.E. Ret. of 7 th & Main	11' x 4'	44.00			
Sta. 21+70.80 ~ Sta. 23+03.15	132.85' x 4'	531.40	Sta. 23+69.49 ~ Sta. 24+85.63	116.14' x 0.50'	58.07			
Basin N.W. Ret. of Seventh St.	16.5' x 4'	66.00	S.W. Ret. Van Buren Alley	15' x 2'	30.00			
N.E. Ret. of Seventh & Main	3.1416 x (12) ² ÷ 4	113.09	S.E. " " " "	15' x 2'	30.00			
2 Basins at N.E. Ret. 7 th & Main	22' x 4'	88.00	Sta. 25+09.05 to Sta. 26+04	94.95' x 0.50'	47.48			
Sta. 23+69.40 ~ Sta. 26+13.55	249.15' x 0.50'	124.57	Sta. 26+65.75 to Sta. 27+48.75	83' x 0.50'	41.50			
Basin at Sta. 26+22.55	16.5' x 4'	66.00	S.W. Ret. of Moorehead Alley	15' x 2'	30.00			
Sta. 26+34.30 ~ Sta. 29+28.87	294.57' x 0.50'	147.28	S.E. " " " "	15' x 2'	30.00			
			Sta. 27+76.25 ~ Sta. 28+73.77	97.52' x 0.50'	48.76			
			Basin at S.W. Cor. Ninth St.	11' x 4'	44.00			
			S.W. Cor. 9 th & Main	3.1416 x (12) ² ÷ 4	113.09			
			Special Inlet Cor. 9 th & Main	11' x 4'	44.00			
		</						

Project Length		
Sta. 0+00 to Sta. 5+43.25		543.25 Lin. Ft.
Sta. 5+68.35 to Sta. 30+12.07		2443.72 Lin. Ft.
Total Project Length		2991.97 Lin. Ft.
Pavement Length		or 0.566 Mi.
2991.97 Lin. Ft. - 1.00 Lin. Ft. (Headers) =		2990.97 Lin. Ft.
T-50 P.V.T.		
2990.97 * .00 ÷ 3		996.99 Sq. Yd.
Approaches		1172.77 "
Total T-50		11147.67 Sq. Yd.
Concrete Widening		
Sheet #7 (between intersections)		2793.50 Sq. Yd.
Approaches		908.94 " "
Total (5"-7½" & 10")		3703.44 " "
Total 10"		300.00 Sq. Yd.
Total 5"-7½"		3403.44 " "
Concrete Curb		
Sheet #7 (between intersections)		4371.84 Lin. Ft.
Approaches		1050.62 " "
Total Conc. Curb		5422.46 Lin. Ft.
Pavement Removal		
Sheet #7 (between intersections)		2793.50 Sq. Yd.
Approaches		1603.83 " "
Total P.V.T. Removal		4397.33 Sq. Yd.
Portland Cement Conc. Base		
3½" x 5½"		693.89 Sq. Yds.

APPROACHES												
SHEET NO.	PAY. REMOVED SQ. YDS.	CONC. BASE 3" THICK SQ. YDS.	CONC. WIDENING SQ. YDS.	CONC. CURB TYPE 1-A LIN. FT.	APPROACH PAV. SQ. YDS.	SPECIAL BASIN EACH	SPECIAL INLET EACH	V.S.R. 12" LIN. FT.	12" TEES	RAISING MANHOLES EACH	NEW M.H. TOPS EACH	CONC. HEADER LIN. FT.
3	733.43	302.48	425.85	472.97	522.22	7	4	130	10	7	7	77.50
4	870.40	386.91	483.99	577.95	655.35	9	3	164	8	12	12	
TOTAL	1603.83	693.89	909.94	1050.92	1177.77	16	7	294	19	19	19	77.50

Concrete sidewalk removal same total
as new concrete sidewalk.