



TYPICAL SECTION ITEM DESCRIPTIONS

- EX. PAVEMENT
- 1-1/4" ~ ITEM 448, ASPHALT CONCRETE, SURFACE COURSE TYPE 1, PG-64-22
- ITEM 407, TACK COAT (APPLIED AT A RATE OF 0.04 GAL/SQ YD)
- 1-3/4" ~ ITEM 448, ASPHALT CONCRETE, INTERMEDIATE COURSE TYPE 2, PG-64-22
- ITEM 407, TACK COAT (APPLIED AT A RATE OF 0.075 GAL/SQ YD)
- 9" ~ ITEM 301, ASPHALT CONCRETE BASE (2 ~ 4-1/2" LIFTS)
- ITEM 408, PRIME COAT (0.35 GAL/SY)
- 6" ~ ITEM 304, AGGREGATE BASE
- ITEM 204, SUBGRADE COMPACTION
- GRAVEL BERM: 6" ~ ITEM 617, AGGREGATE BASE TYPE A, WITH REMAINDER CONSTRUCTED WITH ITEM 203 EMBANKMENT
- ITEM 605, AGGREGATE DRAIN (8"D x 12"W, SPACED EVERY 50') EXTEND TO DAYLIGHT
- NEATLY SAW CUT EX. ASPHALT. APPLY ITEM 407, TACK COAT TO VERTICAL FACE OF EX. PAVEMENT PRIOR TO PLACING NEW PAVEMENT. AFTER PLACEMENT OF FINAL SURFACE COURSE, SEAL JOINT WITH ITEM 705.04, HOT APPLIED JOINT SEALER. COST FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR THE ITEM 202 PAVEMENT REMOVED.