

BOWMAN & ASSOCIATES
59 SECOND STREET
FRAZEYSBURG, OHIO 43822
PH./FAX (614) 828-2204

17-03-02-05-002
4444 BARBERS RD RD

SURVEY DESCRIPTION

FOR

Thelma Cohagan
Parcel 1

PART OF PARCEL

17-03-02-05-000 (0.538 Acres)

Situated in quarter Township 2, T-1-N, R-8-W, Falls Township, Muskingum County, Ohio. Being part of the lands of Thelma Cohagan as conveyed Deed Book 1077 page 472 of the Muskingum County Deed Records, and being described as follows:

Commencing at the Northeast corner of quarter Township 2; thence, S.01°36'17"E. a calculated distance of 3,155.34 feet along the East line of said quarter township to a set rebar on the Southeast corner of the lands, now or formerly, owned by L. Polk, Et Al, (1077/147); thence, N.89°47'57"W. a distance of 779.61 feet along the South line of said Polk lands to a set rebar, BEING THE POINT OF BEGINNING;

thence, N.89°47'57"W. a distance of 209.58 feet along the South line of said Polk lands to a found axle on the Northeast corner of the lands, now or formerly, owned by T. Taft (844/313);

thence, S.10°48'30"W. a distance of 93.19 feet along the east line of said Taft lands to a set rebar;

thence, S.82°15'22"E. a distance of 172.53 feet through the lands of T. Cohagan (1077/472) to a set rebar;

thence, N.89°21'19"E. a distance of 60.44 feet through said Cohagan lands to a set rebar;

thence, N.02°11'20"W. a distance of 113.46 feet through said Cohagan lands to the Point of beginning.

The above described parcel contains 0.538 acres more or less, and is subject to all legal easements and right of ways. The set rebars are 5/8" x 30" rebars with plastic I.D. caps. North is based upon an assumed meridian.

DESCRIPTION APPROVED
FOR AUDITORS TRANSFER

BY APB

4-23-97

Also attached to the above described parcel is a 25 foot wide right of way from County Road 407 (Barkers Run Road) across the lands of T. Cohagan (1077/472) for the purpose of ingress and egress, said right of way is located south of and along the following described lines:

Commencing at the Northeast corner of quarter Township 2; thence, S.01°36'17"E. a calculated distance of 3,155.34 feet along the East line of said quarter township to a set rebar on the Southeast corner of the lands, now or formerly, owned by L. Polk, Et Al, (1077/147); thence, N.89°47'57"W. a distance of 602.01 feet along the South line of said Polk lands to a set rebar; thence, S.17°11'08"E. A distance of 92.26 feet through the lands of T. Cohagan (1077/472) to a set rebar, BEING THE Northeast corner of the attached right of way:

thence, S.83°00'07"W. a distance of 202.03 feet through said Cohagan lands and along the south line of a 0.442 acre parcel to a set rebar;

thence, S.89°21'19"W. a distance of 60.44 feet through said Cohagan lands and along the south line of a 0.538 acre parcel to a set rebar;

thence, N.82°15'22"W. a distance of 172.53 feet through said Cohagan lands and along the south line of a 0.538 acre parcel to a set rebar on the Southeast corner of the lands, now or formerly, owned by T. Taft (844/313);

thence, S.41°22'18"W. a distance of 177.82 feet through said Cohagan lands to a point in the center of County Road 407 (Barkers Run Road) being the terminus point of the attached right of way.

Description was prepared from an actual survey by Bowman & Associates, Stephen M. Bowman, P.S.#7135. April 14, 1997

OFFICE COPY
NOT RECORDABLE


NORTH IS BASED UPON
AN ASSUMED MERIDIAN

SCALE 1" = 140'



SURVEY PLAT FOR THELMA COHAGAN

SITUATED IN QUARTER TOWNSHIP 2, T-1-N, R-6-W, FALLS TOWNSHIP,
MUSKINGUM COUNTY, OHIO. BEING PART OF THE LANDS OF THELMA
COHAGAN AS CONVEYED IN PARCEL 1 OF DEED BOOK
1077 PAGE 472 OF THE MUSKINGUM COUNTY DEED RECORDS.



T. COHAGAN
(1077/472)

DESCRIPTION APPROVED
FOR AUDITORS TRANSFER

BY *ASD*
4-23-97

LEGEND

- IRON PIN FOUND
- ⊕ 5/8" X 30" REBAR SET W/ I.D. CAP
- POINT

I CERTIFY THIS DRAWING WAS PREPARED
FROM AN ACTUAL FIELD SURVEY CONDUCTED
ON APRIL 04, 1997

**OFFICE COPY
NOT RECORDABLE**

BOWMAN & ASSOCIATES
59 SECOND STREET
FRAZEYSBURG, OHIO 43822
PHONE/FAX 614-828-2204
JOB: M-97051 DATE: 04/04/97

PART OF AUDITORS PARCEL
17-03-02-05-000

PARCEL 1	PARCEL 2
T. COHAGAN (1077/472)	T. COHAGAN (1077/472)
0.538 ACRES MORE OR LESS	0.442 ACRES MORE OR LESS