

25-80-17-09
2053 GARA LN

LANDMARK SURVEYS, INC.

A DIVERSIFIED CORPORATION Land Surveying - Land Sales - Land Development - Excavating
727 Cambridge Road, Coshocton, Ohio 43812; e-donaker@usa.net (740) 623-0993 800-842-3264 fax: (740) 623-0997

ACREAGE INVESTMENTS, INC. 4.000 Acres

JD103825

Being 4.000 acres, more or less (*part of #:* 25-25-80-17-09-001) part of Tract 25, Harden Farm, Plat Book 17, pages 140-141, in the southwest quarter of section 17, of township 18 north, range 15 west, Congress Lands East of the Scioto River, in the township of Hopewell, in the county of Muskingum, in the State of Ohio, and more particularly described as follows:

Beginning at a 5/8" steel pin found at the northwest corner of Tract 25, Harden Farm, Plat Book 17, pages 140-141, said 5/8" steel pin found being the TRUE POINT OF BEGINNING;

thence, along the south line of Tract 26, S.89°15'18"E. 700.77' to a 5/8" steel pin found;

thence, through Tract 25 the following 3 courses:

1. thence, S.00°20'11"W. 200.00' to a 5/8" steel pin found;
2. thence, S.89°15'18"E. 418.89' to a 5/8" steel pin found;
3. thence, continuing S.89°15'18"E. 16.72' to a point in TR 286, Gard Lane;

thence, along the north & south quarter line, S.00°20'11"W. 30.00' to a point in TR 286, Gard Lane;

thence, along the north line of Tract 24 the following 2 courses:

1. thence, N.89°15'18"W. 475.91' to a 5/8" steel pin found;
2. thence, continuing N.89°15'18"W. 660.47' to a 5/8" steel pin found;

thence, along the east line of Tract 16, N.00°20'11"E. 230.00' to the TRUE POINT OF BEGINNING, containing 4.000 acres, more or less, including public road right-of-way and is subject to all easements, rights-of-way, or restrictions, whether recorded or implied.

Bearings are based on DB1161/267, N.89°30'59"W. and are for angular calculations only.

Pertinent documents: tax maps, deeds: 1161/267; Plat Book 17, pages 140-141; surveys by: Earl R. Donaker.

Prior deed: DB _____, page _____.

Description and plat by Landmark Surveys, Inc. Earl R. Donaker, Professional Surveyor, #7142, from a survey of the premises in the month of August in the year of our LORD two thousand.

**OFFICE COPY
NOT RECORDABLE**

DESCRIPTION APPROVED
FOR AUDITOR'S TRANSFER
BY *[Signature]*

8-25-2000

THIS PROPERTY IS SUBJECT TO ALL EASEMENTS, RIGHTS-OF-WAY, OR RESTRICTIONS, WHETHER RECORDED OR IMPLIED.

727 Cambridge Road
Coshocton, Ohio 43812


LANDMARK SURVEYS, INC.

EARL R. DONAKER, P.S.


tel: (740) 623-0993
1-800-842-3264

ACREAGE INVESTMENTS, INC.

Tract 25, Harden Farm
Plat Book 17 pg. 140-141
DB _____ pg. _____



All bearings & distances are of record, except as marked.




20' Utility easement and the right of entry to install, repair and maintain is hereby reserved and granted to ALL public utilities both present and future as may be available to any and all property owners. Right of entry shall not be confined to the specified 20'.



Bearings are based on DB1161/207 N. 89°30'59"W and are for angular calculations only.

Pertinent documents: Tax maps:
Deeds: 1161/267
Plat Book 17, pg. 140-141
Surveys by: Earl R. Donaker



OFFICE COPY NOT RECORDABLE

I, Earl R. Donaker, hereby certify that this plat represents a boundary survey pursuant to Chapter 4733-37, Ohio Administrative Code and to be correct to the best of my knowledge and belief.

DESCRIPTION APPROVED FOR AUDITOR'S TRANSFER BY *[Signature]*

8-25-2000

- - 5/8" steel pin found
- ▲ - point

"Remove not the old landmark." Proverbs 23:10

ACREAGE INVESTMENTS, INC.
ACRES: 2.000 & 4.000
SW 1/4, SECTION 17
T 18 N.R 15 W CONGRESS LANDS
EAST OF THE SCIOTO RIVER
TOWNSHIP: HOPEWELL
COUNTY: MUSKINGUM, OHIO
AUGUST, 2000
JD103825