

MUSKINGUM COUNTY



Douglas R. Davis P.E.,P.S. - County Engineer

155 Rehl Road - Zanesville, Ohio 43701

email - mceo@rroho.com

website - www.mceo.org

Phone: 740-454-0155

Fax: 740-455-7180

September 15, 2017

Addendum #1

Air Park Drive & 5 B's Road Resurfacing

The bid proposal has been revised. Bidders are advised that the bid proposal has been revised. The scope of work has changed. Quantities for the resurfacing and related work remain unchanged.

The new bid proposal is denoted at Revision 1 and should be utilized by bidders when submitting bids for the project.

**MUSKINGUM COUNTY, OHIO
 ASPHALT CONCRETE RESURFACING PROPOSAL
 REVISION 1**

ROAD NAME: Air Park Drive (Airport Rd to 5 B's Rd) & 5 B's Road (Air Park Dr to South Point Rd)

Length = 1.30 miles
Width = 24 ft
Thickness = 3 inches

GENERAL INFORMATION AND SPECIFICATIONS

SCOPE OF WORK: The Contractor shall furnish all materials, equipment and tools necessary to complete the asphalt paving complete in place on roadway acceptable to the County Engineer. All materials shall meet current O.D.O.T. Specifications and shall come from a source certified by O.D.O.T. All equipment shall meet current O.D.O.T. Specifications. The contractor shall clean and otherwise prepare the surface for paving. The contractor shall place a butt joint across the entire width of the roadway as directed by the County Engineer to provide a level transition from new asphalt to existing pavement. Contractor shall apply liquid asphalt and seal edges of new to existing pavement at beginning and end of overlay and intersections, including butt joints. All costs related to butt joints, joint sealing, mobilization, and traffic control shall be included in the unit price for 448 Asphalt Concrete, Type 1, Surface Course.

MATERIAL

- 1,373 Tons 448 Asphalt Concrete, Type 1, Surface Course, Furnished
 Hauled, Spread, and Rolled, 1.25 inch avg @ \$ _____ = \$ _____
- 1,922 Tons 448 Asphalt Concrete, Type 2, Intermediate Course, Furnished
 Hauled, Spread, and Rolled, 1.75 inch avg @ \$ _____ = \$ _____
- 1,830 Gallons 407 Asphalt Tack Coat, Furnished & Applied
 (0.1 gal sq. yd.) @ \$ _____ = \$ _____
- 508 Tons 617, Reconditioned Shoulder for Berm, Furnished
 & installed, 2 Ft berm each side @ \$ _____ = \$ _____
- 1.30 Miles 648 Spray Thermoplastic Center Line @ \$ _____ = \$ _____
- 2.60 Miles 648 Spray Thermoplastic Edge Line @ \$ _____ = \$ _____

Bidder Name: _____ **TOTAL = \$** _____

Signed: _____

Print Name: _____

Date: _____