

GENERAL NOTES

COMMENCEMENT OF WORK:

THE CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER, (614) 454-0155 FORTY-EIGHT (48) HOURS PRIOR TO COMMENCING WORK ON THE PROJECT, HOLIDAYS AND WEEKENDS EXCLUDED.

MINIMIZING THE CONSTRUCTION IMPACTS TO THE AREA RESIDENTS AND BUSINESSES IS A PRIMARY CONCERN OF THIS CONTRACT. THEREFORE, THE CONTRACTOR SHOULD PLAN HIS WORK TO PROVIDE THE LEAST DISTURBANCE AND BE PREPARED TO RESPOND TO RESIDENTS CONCERNS IN A PROFESSIONAL AND PROMPT MANNER.

UTILITIES:

LISTED BELOW ARE ALL UTILITIES WHICH MAY BE LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS.

ALLTEL OHIO INC.*
66 N. FOURTH ST.
NEWARK, OHIO 43055
614-349-8873

AMERITECH*
(OHIO BELL TELEPHONE CO.)
ATT: ENGINEERING DEPT.
160 N. SIXTH STREET
ZANESVILLE, OHIO 43701
614-454-3514

CNG TRANSMISSION CORP.*
115 EVERGREEN HEIGHTS DR.
PITTSBURG, PA 15229
412-415-5065 EXT. 6749

COLUMBIA GAS OF OHIO*
2429 LINDEN AVENUE
ZANESVILLE, OHIO 43701
614-452-5467

COLUMBIA GAS TRANSMISSIONS*
11296 E. PIKE RD.
CAMBRIDGE, OHIO 43725
614-432-1600

COLUMBIA GAS TRANSMISSIONS*
1608 HOMER RD. NW
P.O. BOX 34
HOMER, OH 43027
614-892-2552

EAST MUSKINGUM WATER AUTHORITY*
375 RICHARDS RD.
P.O. BOX 2007
ZANESVILLE, OHIO 43702
614-453-0678

NATIONAL GAS & OIL*
1500 GRANVILLE RD.
P.O. BOX 4970
NEWARK, OHIO 43058
614-344-2103

SPRINT/UNITED*
220 S. PARK AVE.
P.O. BOX 311
WARREN, OHIO 44482
330-841-1586

WORLDCOM*
6929 N. LAKEWOOD AVE.
P.O. BOX 21348
TULSA, OK 74117
800-248-0133

BELDEN AND BLAKE
4362 GLENN HIGHWAY
CAMBRIDGE, OH 43725
614-439-5558

GUERNSEY-MUSKINGUM ELECTRIC CO.
17 S. LIBERTY ST.
NEW CONCORD, OHIO 43762
614-826-7661

OHIO OIL GATHERING
P.O. BOX 377
FRAZEYSBURG, OHIO 43822
614-828-2892

OHIO POWER COMPANY
1-800-672-2231

STOCKER AND SITLER INC.
4770 INDIANOLA AVE.
COLUMBUS, OH 43214
614-888-9588

TCI CABLEVISION
737 HOWARD ST.
ZANESVILLE, OHIO 43701
614-450-8315

CONTINGENCY QUANTITIES:

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER. THE ACTUAL WORK LOCATIONS AND QUANTITIES USED FOR SUCH ITEMS SHALL BE INCORPORATED INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

CONSTRUCTION NOISE:

ACTIVITIES AND LAND USE ADJACENT TO THIS PROJECT MAY BE AFFECTED BY CONSTRUCTION NOISE. IN ORDER TO MINIMIZE ANY ADVERSE CONSTRUCTION NOISE IMPACTS, ANY POWER-OPERATED CONSTRUCTION-TYPE DEVICE SHALL NOT BE OPERATED BETWEEN THE HOURS OF 9 PM. AND 6 AM. IN ADDITION, ANY SUCH DEVICE SHALL NOT BE OPERATED AT ANY TIME IN SUCH A MANNER THAT THE NOISE CREATED SUBSTANTIALLY EXCEEDS THE NOISE CUSTOMARILY AND NECESSARILY ATTENDANT TO THE REASONABLE AND EFFICIENT PERFORMANCE OF SUCH EQUIPMENT.

WORK LIMITS:

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

NON-RUBBER TIRED VEHICLES:

ALL NON-RUBBER TIRED VEHICLES SHALL BE PROHIBITED FROM ANY ASPHALT OR CONCRETE STREET. EXCEPTIONS MAY BE GRANTED WHERE SHORT DISTANCES AND SPECIAL CIRCUMSTANCES ARE INVOLVED. REQUEST FOR AN EXCEPTION MUST BE MADE IN WRITING AND ANY DAMAGE OCCURRING SHALL BE REPAIRED TO THE SATISFACTION OF AND AT NO ADDITIONAL COST TO THE OWNER.

SAFETY REQUIREMENTS:

THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE SOLELY RESPONSIBLE FOR COMPLYING WITH THE OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970, OR THE MOST CURRENT VERSION THEREOF, DURING THE CONDUCT AND PERFORMANCE ON AND IN CONNECTION WITH THIS PROJECT.

SIGNS, DRAINAGE STRUCTURES, BUILDINGS, ETC.:

ALL SIGNS, DRAINAGE STRUCTURES, BUILDINGS, OR OTHER PHYSICAL FEATURES DISTURBED OR DAMAGED DURING WORK UNDER THIS CONTRACT SHALL BE RESTORED TO THEIR ORIGINAL CONDITION BY THE CONTRACTOR, AT NO ADDITIONAL COST TO THE OWNER.

ITEM 203 - LINEAR GRADING:

THIS WORK SHALL CONSIST OF SHAPING OR RESHAPING THE SHOULDER AS DIRECTED BY THE ENGINEER TO INSURE A SMOOTH DRAINABLE SURFACE FREE OF ALL IRREGULARITIES. EXCESS EXCAVATION RESULTING FROM THE SHOULDER WORK SHALL BE DISPOSED OF AS DIRECTED BY THE ENGINEER. PAYMENT FOR SHAPING OR RESHAPING THE GRADED SHOULDER AS DESCRIBED SHALL BE INCLUDED IN THE CONTRACT PRICE PER KILOMETER FOR ITEM 203, LINEAR GRADING.

TOTAL CARRIED TO THE GENERAL SUMMARY.

ITEM 203 - LINEAR GRADING 19.90 KM.

* OUPS MEMBER

THERE ARE NO UTILITIES SHOWN ON THE PLANS. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO HAVE ALL UTILITIES LOCATED PRIOR TO COMMENCEMENT OF CONSTRUCTION. UTILITIES DAMAGED DURING WORK UNDER THIS CONTRACT SHALL BE RESTORED TO THEIR ORIGINAL CONDITION BY THE CONTRACTOR, AT NO ADDITIONAL COST TO THE OWNER OF THE UTILITY, MUSKINGUM COUNTY, OR ODOT.