

NOTE
EMBANKMENT shall be completed to the elevation of the roadway subgrade for a distance of 500' beyond the bridge limits for a minimum of 30 days before any construction may begin on the abutments

