

SUMMARY OF QUANTITIES

STATION	EXC.	EMB.	EMB. + 20%	WASTE	BORROW	REMARK
0+00 to 8+00	1564	825	990	574		
8+00 to 16+00	2426	814	977	1449		
16+00 to 25+00	5582	1896	2275	3307		
25+00 to 40+00	8052	2176	2611	5441		
40+00 to 48+00	2385	2188	2626		241	
48+00 to 57+00	1111	532	638	473		
57+00 to 65+23	1629	259	311	1318		
Roadway Total	22749	8690	10428	12562	241	
Creek Change #1	1000	1000	1200		200	Sta. 9 to 13
" " #2	1300	600	720	580		" 4 to 44
Creek Change Total	2300	1600	1920	580	200	
Grand Total	25049	10290	12348	13142	441	

6595.5' L Top Surf
8' W 440
2" T Ton Gravel

BRIDGE AT STATION 7 + 00				
Steel	3700 #	See State Standards		
Cement	60 bbl.	"	"	"
Gravel	36 Yd.	"	"	"
Sand	18 Yd.	"	"	"
Form Lumber	1 M	Asst.		

Length of Project
6595.5 ft.
1.25 miles

STRUCTURES UNDER 20 FOOT SPAN						
Station	Lin. Ft.	Conc. pipe			Exc. Cu. yds	Remarks
	12"	15"	24"	60"		
0 + 07	57				19	
3 + 11	36				1	
9 + 95	39				17	
15 + 58	30				3	
20 + 22	33				8	
23 + 08				42	11	
28 + 13	28				6	
30 + 26	47				12	
35 + 91	26				8	
37 + 36	27				11	
42 + 30					60	
44 + 90		28			10	
Total	323	28	42	60	116	