

GENERAL SUMMARY

CALC. BY THL
DATE 11/1/89
CHKD. BY THL
DATE 11/1/89

MUS CR-500-0.00
CREAMERY ROAD

8
15

SHEET NUMBER									ITEM	ITEM EXT. NO.	GRAND TOTAL PART 1	UNIT	DESCRIPTION
3	4	5	6	7	9	10	11	13					
													ROADWAY
								2800	201	11000	LUMP	LUMP	CLEARING AND GRUBBING
			100						202	38000	2800	LIN.FT.	GUARDRAIL REMOVED
		5.67							203	20000	100	CU.YD.	EMBANKMENT
								437.5	203	60500	5.67	MILE	LINEAR GRADING
									517	72301	437.5	LIN.FT.	RAILING (DEEP BEAM RAIL W/STEEL TUBULAR BACKUP & TYPE 2 STEEL POST & ANCHOR BOLTS), AS PER PLAN
								2412.5	606	13000	2412.5	LIN.FT.	GUARDRAIL, TYPE 5
								20	606	25000	20	EACH	ANCHOR ASSEMBLY, TYPE A
				39				8	606	35140	8	EACH	BRIDGE TERMINAL ASSEMBLY TYPE 4
				1					SPECIAL	690E50100	39	EACH	MAIL BOX SUPPORT SYSTEM, SINGLE
									SPECIAL	690E50200	1	EACH	MAIL BOX SUPPORT SYSTEM, DOUBLE
													PAVEMENT
5,220				136					304	20000	136	CU.YD.	AGGREGATE BASE
1,112									407	10000	5,220	GAL.	TACK COAT
3,518		300							408	10000	1,112	GAL.	BITUMINOUS PRIME COAT
2,475				68					448	15000	3,518	CU.YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, AC-20
									448	16000	2,843	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, AC-20
		50							448	16004	50	CU.YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, AC-20
	740												(FOR DRIVEWAYS)
	3.0								617	10100	740	CU.YD.	COMPACTED AGGREGATE, TYPE A
									617	25000	3.0	M GAL.	WATER
													MAINTENANCE OF TRAFFIC
17.7			112						614	12460	112	EACH	WORK ZONE MARKING SIGN
			20						614	21400	17.7	MILE	TEMPORARY CENTER LINE, CLASS II
			2						616	10000	20	M GAL.	WATER
									616	20000	2	TON	CALCIUM CHLORIDE
													TRAFFIC CONTROL
					5.72	11.44			642	00090	11.44	MILE	EDGE LINE
									642	00290	5.72	MILE	CENTER LINE
							118		644	00500	118	LIN.FT.	STOP LINE
									SPECIAL	619 25000	LUMP		COMPUTER EQUIPMENT FOR TYPE A OFFICE
									614	11000	LUMP	LUMP	MAINTAINING TRAFFIC
									619	15000	LUMP	LUMP	FIELD OFFICE, TYPE A
									623	10000	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES
									624	10000	LUMP	LUMP	MOBILIZATION