



TYPICAL HALF-SECTION
SHOWING EXISTING CONCRETE
AND PROPOSED RESURFACING
Scale: 1" = 1 Ft.

- * ① T-35 1 1/4" Asphalt conc. surface course, Type 'C' (70-85).
* ② B-35 1 1/4" Asphalt conc. leveling course, Using Type 'C' T-35 Mat'l. (70-85)
③ T-30 Bituminous Seal Coat, Sec. M-5.8 MS-2 or MS-4, or Sec. M-5.2 Road Seal
as per Sec. T-30.02. Applied at 5.0 gal. per sq. yd.
* Thicknesses shown are design thicknesses as
described in Sections T-35.01 and B-35.01.



PERSHING ROAD
PROPOSED RESURFACING

DRAWN BY JTG	TRACED BY	APPROVED	DATE SHIPPED 2/27/64
DATE 2-1-64	TCMS 1/1/60	REB. BOOK	UNLAWFUL INVOICE 3/2/64