

GENERAL NOTES

TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS AND THE FOLLOWING REQUIREMENTS;

THE CONTRACTOR WILL BE REQUIRED TO PROVIDE, ERECT, MAINTAIN (IN PROPER POSITION, CLEAN, LEGIBLE, AND IN GOOD WORKING CONDITION) AND REMOVE ALL SIGNS, SIGN SUPPORTS, BARRICADES, DRUMS, AND ALL OTHER TRAFFIC CONTROL DEVICES NECESSARY FOR THE MAINTENANCE OF TRAFFIC.

THE COST OF PROVIDING, INSTALLING, MAINTAINING AND REMOVING ALL TRAFFIC CONTROL DEVICES REQUIRED TO MAINTAIN TRAFFIC DURING CONSTRUCTION INCLUDING SIGNS, SIGN SUPPORTS, DRUMS, AND BARRICADES SHALL BE INCLUDED IN THE LUMP SUM PER ITEM 614 "MAINTAINING TRAFFIC".

THE CONTRACTOR SHALL MAINTAIN TRAFFIC AT ALL TIMES IN ACCORDANCE WITH THE REQUIREMENTS OF SPEC. 614. TWO-WAY FOUR LANE TRAFFIC SHALL BE MAINTAINED AT ALL TIMES ON U.S. 22 EXCEPT FOR A SHORT PERIOD OF NOT MORE THAN 20 CONSECUTIVE DAYS WHILE CONNECTIONS TO C.R. 719 ARE COMPLETED. ONE LANE OF THE NORTHBOUND LANES ON EXISTING U.S. 22 MAY BE CLOSED IN ACCORDENCE WITH (C-21) OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

ACCESS TO ALL ADJOINING PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER FOR MAINTENANCE OF TRAFFIC.

ITEM 404	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	20 C.Y.
ITEM 410	TRAFFIC COMPACTED SURFACE TYPE A OR B	20 C.Y.
ITEM 616	WATER	10 M.GAL.
ITEM 616	CALCIUM CHLORIDE	1 TON

ALL OTHER WORK REQUIRED FOR TRAFFIC MAINTENANCE SHALL BE INCLUDED WITH PAYMENT FOR ITEM 614 MAINTAINING TRAFFIC.

CALC	PCE	11-87
CHK	ROB	11-87

FHWA REGION	STATE	PROJECT	
5	OHIO		

MUSKINGUM COUNTY
MUS - CR. 719

