

SUMMARY OF QUANTITIES

[illegible]

EXCAVATION
PAVEMENT (TYPICAL SECTION DIMENSION)
GUARD RAIL
FINISHING SHOULDERS, SLOPES, & DITCHES. LIN. FT. OF ROADWAY.
LOOSE STONE FOR APPROACHES
EXTRA PAVEMENT FOR CURVE AT NORTH APPROACH
CHANNEL EXCAVATION

TYPE "C"

1670	CU. YDS.
4271	SQ. YDS.
250	LIN. FT.
2412	LIN. FT.
25	CU. YDS.
65	SQ. YDS.
1000	CU. YDS.

SUMMARY OF LOOSE STONE		
STA.	SIDE	CU. YDS.
00+79	LEFT	5
1+87	RIGHT	5
5+36	LEFT	5
8+62	LEFT	5
12+50	RIGHT	5
TOTAL		25

SUMMARY OF TYPE "E" GUARD RAIL			
FROM STA.	TO STA.	SIDE	LIN. FT.
END CONC. BRIDGE	23+00	RIGHT	100
00+00	1+00	RIGHT	100
00+00	00+50	LEFT	50
TOTAL			250

SUMMARY OF		EXCAVATION AND EMBANKMENT				
FROM STA.	TO STA.	CUBIC YARDS				BORROW
		EXCAV.	EMB.	EMB.+	WASTE	
00+00	3+65	325	160	200	125	
3+65	13+50	917	2	3	914	
13+50	19+50	268	79	99	169	
19+50	24+12	160	125	156	4	
TOTALS		1670	366	458	1212	