

GENERAL NOTES: (Pavement Marking and Signing)

ITEM 857 REMOVE & REERECT GROUND MOUNTED INSTALLATION:

Ground mounted signs and supports shall be carefully removed where indicated on the plans and reerected as shown. To assure maintenance of adequate traffic control at all times, no signs shall be removed without the approval of the Engineer.

Reerection may require field drilling and any necessary hardware shall be furnished by the Contractor. The existing drive post & sign face shall be reused in the new installation.

If the supports are damaged, the Contractor shall furnish new N° 3 posts as part of this bid item. Payment will be at the contract unit price for each installation removed and reerected.

ITEM 857 SIGNS ERECTED, FLAT SHEET:

The City of Zanesville shall furnish the R-31A-36 lane use sign for erection by the Contractor. It shall be picked up at the Street Division Garage at 1084 Central Ave.

MUS- CITY OF ZANESVILLE
TAYLOR STREET

FHWA REGION	STATE	PROJECT
5	OHIO	

2-A
41

CALCULATED BY B.M. 3-28-79
CHECKED BY J.D. DATE 5-27-79

SUB - SUMMARY

QUANTITIES - PAVEMENT MARKING AND SIGNING

SIDE	MARK	STATION TO STATION	847	621	Item 847			847	621	Item 857			Reference N°	Size
			8" White Channelizing Line 847.10 Type A LIN. FT.	24" Yellow Broad Transverse Line LIN. FT.	Lane Arrow 847.10 Type A EACH	Word ONLY on Pavement 847.10 Type A EACH	24" stop lines 847.10 Type A LIN. FT.	6" Crosswalk Lines 847.10 TYPE A LIN. FT.	4" Center Lines Double Spd MILES	Signs Erected, Flat Sheet SQ. FT.	Ground Mounted Supports N° 3 Post Driven LIN. FT.	Remove & Reerect Ground Mounted Installation EACH		
Lt.	1-L	0+33 Blue Ave.					15							
Lt.	2-L	0+33 Clarendon Ave.					12							
Lt.	3-L	0+33 Marion St. Rt.					13							
Lt.	4-L	0+32 Marion St. Lt.					12							
Lt.	5-L	0+33 Bell St.					22							
Lt.	6-L	0+31 Wilmer St. Lt.					13							
Lt.	7-L	0+29 Wilmer St. Rt.					14							
Rt.	8-L	41+96 M					27							
Lt./Rt.	9-L	0+23+0+29 Blue Ave.						80						
Lt./Rt.	10-L	0+23+0+29 Clarendon Ave.						60						
Lt./Rt.	11-L	0+23+0+29 Marion St. Rt.						60						
Lt./Rt.	12-L	0+22+0+28 Marion St. Lt.						60						
Lt./Rt.	13-L	0+23+0+29 Bell St.						111						
Lt./Rt.	14-L	0+20+0+26 Wilmer St. Lt.						70						
Lt./Rt.	15-L	0+18+0+24 Wilmer St. Rt.						78						
Lt./Rt.	16-L	42+06+42+00 M						128						
☺	17-L	0+33-0+84 Blue Ave.							0.010					
☺	18-L	24+33-40+00 M							0.297					
☺	19-L	0+33-0+85 Clarendon Ave.							0.010					
☺	20-L	0+33-0+37 Marion St. Rt.							0.001					
☺	21-L	0+32-0+75 Marion St. Lt.							0.008					
☺	22-L	0+33-1+20 Bell St.							0.016					
☺	23-L	0+29-0+48 Wilmer St. Rt.							0.004					
☺	24-L	0+31-0+37 Wilmer St. Lt.							0.001					
☺/Lt.	25-L	40+00-41+00 M		25					0.038					
Lt.	26-L	41+00-41+96 M							0.018					
Lt.	27-L	41+31 M												
Lt.	28-L	41+66 M												
Rt.	29-L	41+20-41+96 M	76											
Lt.	1-S	0+33 Blue Ave.											R-1-30	25x2.5
Lt.	2-S	0+33 Clarendon Ave.											R-1-30	25x2.5
Lt.	3-S	0+33 Marion St. Rt.											R-1-30	25x2.5
Lt.	4-S	0+32 Marion St. Lt.											R-1-30	25x2.5
Lt.	5-S	0+33 Bell St.											R-1-30	25x2.5
Lt.	6-S	0+31 Wilmer St. Lt.											R-1-30	25x2.5
Lt.	7-S	0+29 Wilmer St. Rt.											R-1-30	25x2.5
Rt.	8-S	41+00 M								7	13		R-31A-36	3x2.5
TOTALS			76	25	1	1	128	647	0.40	7	13	7		

GENERAL SUMMARY-PAVEMENT MARKING AND SIGNING

Item No	Carried From Table This Sheet	TOTALS	UNIT	DESCRIPTION
621	0.40	0.40	Miles	Center Lines
847	647	647	Lin. Ft.	6" Crosswalk Lines 847.10 Type A Inlaid
857	7	7	Sq. Ft.	Signs Erected, Flat Sheet
857	13	13	Lin. Ft.	Ground mounted supports N° 3 post driven
857	7	7	Each	Remove and Reerect Ground Mounted Installation
847	76	76	Lin. Ft.	8" White channelizing line 847.10 Type A Inlaid
621	25	25	Lin. Ft.	Broad Transverse Line
847	1	1	Each	Lane arrow 847.10 Type A Inlaid
847	1	1	Each	Word ONLY on pavement 847.10 Type A Inlaid
847	128	128	Lin. Ft.	24" Stop Lines 847.10 Type A Inlaid