

ROADWAY DRAINAGE (D)

Item No.	Station		Side	Pipe for Storm Sewers under Roadway		Outlet Pipe for Storm Sewers	
	From	To		Size	Length	Size	Length
1-D	1117+00		Rt	30"	46		
2-D	1120+00		Rt	30"	48		
3-D	1122+75		Rt	30"	48		
4-D	1125+50		Rt	30"	26		
Totals					120		168

*Left end of each pipe to be blocked with a cemented stopper.

CATCH BASINS (I)

Item No.	Station		Side	Catch Basins	
	From	To		Size	Units
1-I	1117+00		Rt	1	
2-I	1120+00		Rt	1	
3-I	1122+75		Rt	1	
4-I	1125+50		Rt	1	
Total				4	

CONCRETE CURB & GUTTER (C)

Item No.	Station		Side	Type 4 Integral Concrete Curb & Gutter	
	From	To		Length	Units
1-C	1115+00	1126+00	Rt	1080	
Total				1080	

DRIVES AND APPROACHES (A)

Item No.	Station		Side	5' WBMd. Aggr. for Base Gr. Surf. from Approach		Pipe for Driveway		Elorap Type A		Details on Sheet No.
	From	To		Size	Length	Size	Length	Size	Length	
1-A	1116+20		Lt	19.6	14.0	32	31	6	*	
2-A	1125+66		Lt	2.3	13.5	32	31	6	*	
Totals				40.9	27.5	32	31	6		

* 30 Sq Yds. each end

PIPE REMOVAL (R)

Item No.	Station		Side	Remove & Store Pipe for Signs	
	From	To		Size	Length
1-R	1116+20		Lt	16	
2-R	1125+82		Lt	18	
Total				34	

PAVEMENT REMOVAL (P)

Item No.	Station		8" PC Conc. Pavement		
	From	To	Length	Width	Sq Yds
1-P	1115+00	1126+00	1100	16	1955.6
Total					1955.6

STRUCTURES 20' SPAN & UNDER

Item No.	Station		Description	Details on Sheet No.
	From	To		
19	1118+90.7		Std. 30"x154'-0" Pipe Culvert	154
20	1125+08.5		Std. 48"x82'-0" Pipe Culvert	156

