

Sta. 1264+11.09 Marker to be furnished & erected on Lt. by the State of Ohio before acceptance of this project.

STA. 1264+11.09 { END FAP NO. 633-G(1)
END S. H. I SEC. I PT.

Proposed Curve
PI Sta. 1257+54.23
 $\Delta = 14^{\circ}04'$ Lt
 $D = 1^{\circ}10'$
 $R = 4911.08'$
 $T = 605.90'$
 $L = 1205.72'$
PC = Sta. 1251+48.33
PT = Sta. 1263+54.05



PAVEMENT REMOVAL (P)					
Item No.	Station		Removal of 8" P.C. Concrete Pavt.		
	From	To	Length	Width	Sq.Yds
1-P	1258+18	1262+13	402	16	714.7
2-P	1262+13	1262+93	81	23.5	211.5
3-P	1262+93	1264+11.09	118.09	33.5	439.6
Total					1365.8

CATCH BASINS (I)					
Item No.	Station	Side	Std Catch Basins		
			No. 1-2 Units	No. 3 Modified Units	No. 4-D Modified Units
1-I	1259+25	Rt.		1	
2-I	1263+00	Lt.	1		
3-I	1263+00	Rt.		1	
4-I	1263+79	Lt.			1
Total			1	2	1

DRIVES & APPROACHES (A)					
Item No.	Station	Side	5" W.B. Macadam		Details on Sheet No.
			Surf 17'10" Sq. Yds	To Bound Side Approach Cu. Yds	
1-A	1259+00	Lt.			47
2-A	1263+34	Lt.			48
3-A	1265+50	Rt.	22.2	18	
Totals			22.2	18	

ROADWAY DRAINAGE (D)							
Item No.	Station		Side	12" Pipe for Rdway Drainage	12" Pipe for S.S. under Pavt.	12" Outlet Pipe for Rd. Drng.	Pipe Specials
	From	To		Lin. Ft.	Lin. Ft.	Lin. Ft.	12"-15" Bend Units
1-D	1258+16	1259+25	Rt.		78		1
2-D	1261+50	1262+99	Lt.	132		20	
3-D	1263+00		Rt.		42		
4-D	1263+00	1263+79	Lt.		76		
Total				132	196	20	1

PIPE REMOVAL (R)			
Item No.	Station	Side	Remove & dispose of Pipe
			Var. Sizes Lin. Ft.
1-R	1260+12	Rt.	164
Total			164

CONCRETE CURB & GUTTER (C)				
Item No.	Station		Side	Type 4 Conc. Curb & Gutter Lin. Ft.
	From	To		
1-C	1258+00	1258+30.75	Rt.	80.8
2-C	1259+02.25	1263+05	Rt.	375.7
3-C	1263+70	1264+00	Rt.	60
Total				516.5

GUARD RAIL (G)					
Item No.	Station		Side	Type Guard Rail Lin. Ft.	Remove & Store Ex. Guard Rail Lin. Ft.
	From	To			
1-G	1258+18	1258+98	Lt.		84
2-G	1259+00	1265+40	Rt.	740	
3-G	1263+87	1264+73	Rt.		86
4-G	1265+60	1269+60	Rt.	400	
5-G	1265+79	1269+01	Rt.		322
Total				1140	492

STRUCTURES 20 FT. SPAN & UNDER				
Struc. No.	Station	Description		Details on Sheet No.
		From	To	
3.4	1258+46.1	30"x162'-0" & 30"x76'-0"	Pipe Culverts	161
3.5	1260+29	Remove Exist. 24"x42.8" C.I.P. Culvert incl. Headwalls		162

Excavation = 732 Cu Yds
Embankment = 36,832 Cu Yds
Emb. +12% 41,252 Cu Yds

