

ROADWAY DRAINAGE (D)									
Item No	Station		Side	Rwy Drg Pipe-Lin Ft		Outlet Pipe for R.D. Lin Ft	R.D. Pipe under Drives Lin Ft	Sewer under Drives Lin Ft	Pipe Specials Units
	From	To		12"	18"				
1-D	1170+00	1170+68	Rt	72					
2-D	1170+74		Rt			27			
3-D	1173+50		Rt			40			
4-D	1176+00		Rt			26			
5-D	1176+37		Lt					46	1
6-D	1175+73	1179+00	Lt		301		20		2
7-D	1179+00		Rt				26	1	
8-D	1179+00	1181+00	Lt			194			3
9-D	1173+60		Lt			72			
Totals				72	301	194	93	72	2 2 1 3

CATCH BASINS (I)					
Item No	Station	Side	Catch Basins		
			Std No 3	Std No 5	Std No 7
1-I	1170+74	Rt	1		
2-I	1173+50	Rt	1		
3-I	1176+00	Rt	1		
4-I	1176+37	Lt		1	
5-I	1179+00	Rt	1		
6-I	1173+43	Lt			1
Total			4	1	1

CONCRETE CURB & GUTTER (C)				
Item No	Station		Side	Type 4 Integral Conc Curb & Gutter Lin. Ft.
	From	To		
1-C	1170+00	1170+98	Rt	83
2-C	1171+35	1181+00	Rt	950
Total				1033

DRIVES & APPROACHES (A)					
Item No	Station	Side	5" W.B. Macadam Surf Tr Sq Yds	App for 18" Side Appr. Cu Yds	12" Pipe for Drives or Wys Lin Ft
1-A	1171+29	Lt	267	200	36
2-A	1171+29	Rt			39
3-A	1173+01	Lt			40
4-A	1176+20	Lt	160	110	
Total			427	31	36

MASONRY REMOVAL (M)			
Item No	Station	Side	Remove exist Catch Basin Cu Yds
1-M	1173+43	Lt	1.0
Total			1.0

GUARD RAIL (G)				
Item No	Station		Side	Type Guard Rail Lin. Ft
	From	To		
1-G	1174+48	1177+52	Rt	304
2-G	1175+45		Lt	17
3-G	1175+50		Lt	16
4-G	1175+93		Lt	17
5-G	1175+98		Lt	16
Total				304 66

PAVEMENT REMOVAL (P)				
Item No	Station		Removal of Exist 8" P.C. Concrete Pavement Length Width	Sq Yds
	From	To		
1-P	1170+26	1181+00	1025 16	1822
Total				1822

PIPE REMOVAL (R)			
Item No	Station	Side	Remove & Store Pipe Various Sizes Lin. Ft.
1-R	1173+50	Lt	98
2-R	1174+80	Lt	16
Total			114

STRUCTURES 20' SPAN & UNDER			
Struct No	Station	Description	Details on Sh. No.
25	1170+15	24' x 152' Pipe Culvert	158
26	1175+70	7' x 5' x 122' Large Box Culvert	156

