

TRAFFIC NOTE

Embankment from Sta. 555+50 to 558+50 to be placed in 3 operations.
 1st. The embankment on the right shall be completed to the level of the present pavement. This embankment shall then be surfaced with T-10 to a minimum width of 15 ft. from edge of present pavement.
 2nd. The embankment on the left shall then be brought to grade with a minimum top width of 22 ft. and surfaced with T-10. Traffic to be maintained on surface of 1st. operation.
 3rd. Place balance of embankment to full width and grade. Traffic to be maintained on surface of 2nd. operation.

Hub 500 45' Hub
 P.C. 561+74.69

DRIVES & APPROACHES

Item	Station	Side	12" Pipe	18" Pipe	Detail Sheet	1-17 Cu. Yds.
1-A	558+93	R				4
2-A	560+73	L	20		48	9
4-A	562+60	R			54	28
5-A	564+41	R				4
6-A	567+74	L	20			4
Totals			40			49

SYMPHORICARPOS VULGARIS (CORALBERRY)			
FROM STA.	TO STA.	SIDE	NO. OF PLANTS
556+25	556+75	LEFT	130
556+25	557+00	RIGHT	95
TOTAL			225

LONICERA JAPONICA HALLEANA (HALL'S HONEY SUCKLE)			
FROM STA.	TO STA.	SIDE	NO. OF PLANTS
560+25	562+25	LEFT	175
TOTAL			175

FED. RD. DIST. No.	STATE	FED. AID PROJ. No.	FISCAL YEAR
10	OHIO	NR125-Unit 3	1936

S.H. No. 1	SEC. R (Pt) & Q (Pt)
MUSKINGUM COUNTY	

VINCA MINOR & SOD COMBINED.

From Sta.	To Sta.	Side	Sq. Yds.
559+08	562+35	Rt	642
Total			642

Note: For details and supplemental specifications on salvaging Vinca Minor and sod combined, see Typical Section Sheet on Roadside Improvement.

From Station	To Station	Side	No. Poles
556+25	556+75	L	130
556+25	557+00	R	95
560+25	562+25	L	175
TOTAL			400

ROADWAY DRAINAGE (DITCH ELIMINATION)

Item	From Sta.	To Sta.	Side	Lin. Ft.	12" Perforated Corrugated Metal Pipe	Remarks
1-D	558+25	559+03	Right	78		Drive Sta. 558+83 to Sta. 559+03
2-D	559+03	559+05	Right			
3-D	559+05	562+85	Right	380		Drive through Sta. 562+15 to Sta. 562+85
4-D	562+85	562+87	Right			
5-D	562+87	564+51	Right	164		Drive Sta. 564+31 to Sta. 564+51
6-D	564+51	564+59	Right	8		
TOTALS				670	2	

Pavement Removal

Item	From Sta.	To Sta.	Side	Lin. Ft.	Sq. Yds.	L.F. Curb
1-PE	557+75	567+00		925	1542	1650
Total					1542	1650

ROADWAY DRAINAGE (PAVEMENT)

ITEM NO.	STATION	SIDE	SPEC. 7 CATCH BASIN 48" SIDE EACH		6" CMP LIN. FT ★ LENGTHS			30° DIPS 6" CMP	DRAIN BASIN EACH	TYPE DRAIN B. OUTL. LIN.
			A	B	C	1	2			
1-PD	556+10	L	1	4	40	10	2			
2-PD	256+10	R	1	4	12	10	2			
3-PD	260+10	R							1	8
4-PD	260+10	L							2	10
TOTALS			2	8	52	20	4		2	