

PI. = 536+63.61
= 38°-55'-43" Lt.
= 0°-48'
= 2531.12'
= 4366.03'
= 7161.97'
= 434.12'

DRIVES & APPROACHES (A)

Item No.	Station	Side	Type	9" R.C.C. Pavement Sq. Yds.	Type 4-A Int. Curb Lin. Ft.	1-17 Aggregate Cu. Yds.	Pipe for Drives Lin. Ft.	8-20 Waterbound Mac. Base Course Sq. Yds.	7-32 Bit. Surface Treatment Sq. Yds.	Detail on Sheet
1-A	565+61.8	Rt.	Lt.	684.48	71.88	8	110	1178.15	1178.15	129
Totals				684.48	71.88	8	110	1178.15	1178.15	

CURB & GUTTER (C)

Item No.	Station	Side	Type 4-Comb Curb & Gutter Lin. Ft.	Type 4-A Integral Conc. Curb Lin. Ft.
1-C	564+00 to 565+06.55	Lt.		106.55
2-C	564+00 to 565+06.55	Rt.	106.55	
3-C	566+21.16 to 574+00	Lt.		778.84
4-C	566+21.16 to 574+00	Rt.	778.84	
Totals				885.39

PAVED GUTTER (PG)				
Item No.	Station		Side	Type / Lin. Ft.
	From	To		
1-PG	564+50	572+89	Lt.	670
2-PG	570+50	572+00	Rt.	168
3-PG	573+08	574+00	Lt.	90
4-PG	572+99	574+00	Rt.	114
Total				1042

STRUCTURES 20' SPAN & UNDER

Struc. No.	Station	Type	Size	Length	Proposed Type	Size	Length	Details on Sheet
6	565+61.8				Pipe	18" 104' 0"	167	
7	572+91				S.B.C.	5' x 4'	271' 0"	168

SODDING (X)

Item No.	Station	Side	Location	Sodding Sq. Yds.
1-X	564+00 to 564+50	Lt.		50
2-X	565+00 to 565+50	Rt.		50
3-X	565+85 to 566+50	Lt.		65
4-X	566+50 to 570+50	Rt.		403
Total				574

GUARD RAIL				(G)
Item No.	Station		Side	New Lin. Ft.
	From	To		
1-G	571+00	574+00	Lt.	300
2-G	571+00	574+00	Rt.	300
Total				600

REMOVALS (R)

Item No.	Station	Side	Pipe Removed & Stored 15" & Under Lin. Ft.	Detail on Sheet
1-R	565+61.8	Lt.	20	129
2-R	565+61.8	Rt.	35	129
Total				55

DRAINAGE (D)

Item No.	Station	Side	Std #3 C. B. Units	12" Pipe for S.S. Outlet Lin. Ft.	12" Pipe for S.S. Outlet Lin. Ft.	12" x 30" Bend for S.S. Outlet Lin. Ft.	12" x 6" Tee for R.U. Type 'A' Lin. Ft.	6" Pipe for R.U. Type 'A' Lin. Ft.	Riprap for R.U. Type 'A' Sq. Yds.	6" x 6" Tee for R.U. Units
1-D	564+00 to 574+00	Lt.							1000	
2-D	564+00 to 574+00	Rt.							1000	
3-D	565+00	Rt.	1	53						1
4-D	568+50	Rt.	1	38	38	2				2
5-D	571+50	Rt.	1	38	100	2				2
Totals				3	129	138	4	3	2000	4

SIDEWALK & STEPS (S)

Item No.	Station	Side	4" Conc. Sidewalk Sq. Ft.	Concrete Steps Lin. Ft.	Detail on Sheet
1-S	565+61.8	Rt.	1368	44	129
Total				1368	44

Seeding 19,454 Sq. Yds.
Excavation 10,173 Cu. Yds.
Embankment 58,700 Cu. Yds.
Emb +20% 70,440 Cu. Yds.