

REMOVALS			(R)
Item No	Station	Side	Structure 20' Span & under Unit
1-R	240 App.		4'x3'x46' Conc. Box
Total			1

STRUCTURES 20' SPAN & UNDER								
Struc. No	Station	Present			Proposed			Details on Sheet
		Type	Size	Length	Type	Size	Length	
13	632+45.4				Pipe	48"	122'-0"	136
14	634+00				L.B.C	7'x5'	166'-0"	174

GUARD RAIL			(G)
Item No.	Station		Side Lin. Ft.
	From	To	
1-G	627+95	632+32.5	Rt. 437.5
2-G	630+126.5	699+350.4	Lt. 517.5
3-G	Approach to R.R.	633+05.21	Lt. 412.5
4-G	632+57.5	634+00	Rt. 142.5
Total			1367.5

JODDING					(X)
Item No.	Station		Side	Location	Soddy Sq. Yds.
	From	To			
1-X	630+50	632+00	Rt.		147
2-X	632+65	634+00	Rt.		112
Total					259

CURB REMOVAL			
Station		Side	Curb Removal Station Ltn. F.
From	To		
630+64	634+00		740
Total			740

ITEM L-14 PLANTING TREES			
Key Scientific Name	Common Name	Size	Quantity
Pinus Nigra	Austrian Pine	4'-5" B&B 16" Ball	6