



THE FAMOUS Y BRIDGE

OFFICE OF

MUSKINGUM COUNTY ENGINEER

LOREN C. CAMP, ENGINEER

DDN PAISLEY, ADMINISTRATIVE ASSISTANT

ZANESVILLE, OHIO 43701

Beginning at a stone at the Southwest corner of the Northwest quarter of section 12; thence along the west line of said section S 1° 55' 09" E (173.15) feet to the center line of Interstate 70, at Sta. 375 + 01.50 as recorded in plat book 10 page 59 in the Muskingum County records; thence with the center line of said Interstate N 67° 16' 51" E (1177.75) feet to the point of curvature at Sta. 386 + 79.25; thence with said curve to the right to a point in said curve, which chord on said curve bears N 68° 10' 31" E 670.72 to a point on curve at Sta. 393 + 50.00 and said point on curve is also on the center line of Co. Rd. 82 at Sta. 20 + 00.00 as recorded in the above described plat; thence leaving said Interstate and with the center line of said County Road 82 N 20° 09' 20" W (76.05) feet to the point of curvature of a curve to the right with a radius of (636.62) feet an arc length of (407.40) feet and a chord which bears N 01° 49' 21" E (400.48) feet; thence N 16° 30' 40" E (39.55) feet to Sta. 25 + 23.00 and said point being on the south right-of-way line of Baltimore and Ohio Railroad, (50) feet left of Sta. 3619 + 63 of said railroad's track maps; thence along the south right-of-way line of said railroad and leaving the center line of said County Road N 73° 29' 20" W (50.00) feet to the true place of beginning for the property herein to be described; thence continuing along the south right-a-way line of said railroad N 73° 25' 15" W (51.52) feet to a point passing over the center line of proposed Co. Rd. 82 at (25.76) feet; thence leaving the south right-of-way line N 2° 34' 55" E (103.06) feet to a point on the north right-of-way line of said railroad; thence along the north right-of-way of said railroad S 73° 25' 15" E (51.52) feet to a point passing over the proposed center line of County Road 82 at (25.76) feet; thence leaving said north right-of-way S 2° 34' 55" W (103.06) feet to the place of beginning containing (0.118) acres.

This description written December 17, 1979 by Loren C. Camp Reg. Surveyor

No. 5843.