

Linn Engineering, Inc.

Civil Engineering Consultants 740-452-7434 • FAX 740-452-5198 534 Market Street • P.O. Box 2086 • Zanesville, Ohio 43702-2086

Situated in the State of Ohio, County of Muskingum, Township of Harriso Frounded and Oserbed as follows:

Being a part of the north balfactory.

particularly described as follows:

Beginning for reference at the southwest corner of the East Half of the Northwest Quarter of Section

thence along the west line of said Section 30 and the east line of lands now owned by K. Komaromy (DR 1019-269) North 03 degrees 27 minutes 25 seconds East 1298.43 feet to a point in the center line of Butterbean Ridge Road and the principal place of beginning;

thence continuing along said section line and said Komaromy's east line North 03 degrees 27 minutes 25 seconds East 42.23 feet to an iron pipe found;

thence continuing along said section line and said Komaromy's east line and the east line of lands now owned by C. Kelly (DR 1129-367) North 02 degrees 29 minutes 45 seconds East 1364.32 feet to an iron pin set on the south line of lands now owned by S. Wolfe (DR 1067-261) and the north line of said Section 30;

thence along said Wolfe's south line South 87 degrees 05 minutes 49 seconds East 1218.86 feet to a 30 inch oak tree on the southwest corner of lands now owned by A. Reid (DR 1085-407) and the mid-section line;

thence along said Reid's south line South 87 degrees 05 minutes 49 seconds East 1321.88 feet to an iron pin found on the northwest corner of lands now owned by E. Rognon (DR 454-680);

thence along said Rognon's west line South 02 degrees 22 minutes 16 seconds West 1350.85 feet to a stone found on the north line of lands now owned by M. Barstow (DR 1048-496), passing the centerline of Butterbean Ridge Road at 33.39 feet;

thence along said Barstow's north line North 87 degrees 23 minutes 04 seconds West 661.04 feet to an iron pin found on the northeast corner of lands now owned by S. Elson (DR 1018-378); thence along said Elson's north line the following four courses:

- 1) North 87 degrees 46 minutes 29 seconds West 652.36 feet to an iron pipe found on the midsection line, passing the centerline of Butterbean Ridge Road at 507.82 feet;
- 2) South 02 degrees 01 minutes 14 seconds West 3.00 feet along the mid-section line to an iron pin set on the southeast corner of the north half of the east half of the Northwest Quarter of Section 30;
- 3) North 87 degrees 04 minutes 20 seconds West 669.27 feet to an iron pin set at the edge of
- 4) South 02 degrees 55 minutes 40 seconds West 12.63 feet to a point on the centerline of Butterbean Ridge Road;

thence along said Elson's north line and the centerline of Butterbean Ridge Road the following six courses:

- 1) South 83 degrees 42 minutes 11 seconds West 236.66 feet to a point;
- 2) South 82 degrees 29 minutes 52 seconds West 195.99 feet to a point;
- 3) North 83 degrees 23 minutes 40 seconds West 59.51 feet to a point;
- 4) North 66 degrees 06 minutes 36 seconds West 42.78 feet to a point;
- 5) North 54 degrees 43 minutes 06 seconds West 34.84 feet to a point;
- North 43 degrees 07 minutes 29 seconds West 8.72 feet to the principal place of beginning, containing 80.05 acres, more or less, subject to all legal road right of ways and applicable easements, written or implied.

Bearings are based NAD 83, Ohio State Plane Coordinate System, South Zone as per GPS observations.

Iron pins set are 5/8 inch diameter by 30 inch long rebar with plastic identification caps.

Date

This description is written based on an actual field survey completed on March 8, 2000 by Jack D. Newcome, Reg. No. 7321.

Reg. No.

Parcel No.: All of: 20-20-50-30-02-000 (40.99 ac.) All of: 20-20-50-30-06-000 (39.06 ac.) JACK D.

NEWCOME
S-7321

SOUTH SIRVE

168 APTOMATYS 1973 168 APTOMATYS 1973 167 APTOMATYS 1974 167 APTOMATYS

