

25-16-07-07-004
9806 HIDDEN SPRINGS



EARL R. DONAKER
PROFESSIONAL SURVEYOR
LANDMARK SURVEYS

727 Cambridge Road
Coshocton, Ohio 43812

1-800-842-3264
(614) 623-0993

FRED & LOVINA HERSHBERGER
5.411 Ac. +/- TRACT II

Being 5.411 acres, more or less, part of parcel number: 25-16-07-07, in the west 1/2 of the northwest quarter of section 7, in the second quarter of township 1 north, range 9 west, United States Military Lands, and in the township of Hopewell, in the county of Muskingum, in the state of Ohio and more particularly described as follows:

Commencing at a 5/8" steel pin set at the southeast corner of the west half of the northwest quarter of section 7;

thence, with the north & south eighth line, the following 6 courses:
1. thence, N.02°03'48"W. 221.12' to a point;
2. thence, continuing N.02°03'48"W. 261.38' to a 5/8" steel pin set;
3. thence, continuing N.02°03'48"W. 284.55' to a point;
4. thence, continuing N.02°03'48"W. 302.08' to a point;
5. thence, continuing N.02°03'48"W. 326.00' to a 5/8" steel pin set;
6. thence, continuing N.02°03'48"W. 258.75' to a point, said point being the TRUE POINT OF BEGINNING;

thence, through the property of Fred & Lovina Hershberger, 1047/74, the following 3 courses:

1. thence, S.88°12'50"W. 502.05' to a 5/8" steel pin set;
2. thence, continuing S.88°12'50"W. 400.00' to a 5/8" steel pin set;
3. thence, continuing S.88°12'50"W. 30.00' to a point;

thence, with Hidden Springs Road, T.R. 292, N.02°12'15"E. 252.84' to a point;

thence, through the property of Fred & Lovina Hershberger, 1047/74, the following 3 courses:

1. thence, N.87°48'17"E. 30.00' to a 5/8" steel pin set;
2. thence, continuing N.87°48'17"E. 400.00' to a 5/8" steel pin set;
3. thence, continuing N.87°48'17"E. 483.22' to a point;

thence, with the north & south eighth line, S.02°03'48"E. 258.75' to the TRUE POINT OF BEGINNING, containing 5.411 acres, more or less, including public road right-of-way and is subject to all easements, rights-of-way, or restrictions, whether recorded or implied.

Bearings are based on Deed Book 1047, page 74.
All 5/8" steel pins set are 30" long.

Prior deed: 1047/74.

Pertinent documents: tax maps: Deeds: 1043/621, 1012/250, 752/263, 1019/77, 574/735, 786/37, 1001/410, 971/72, 753/105, 906/176, 492/150, 1033/265, 834/308, 1030/424, 1041/73, 590/54, 1028/558, 1028/565, 805/38, 848/229, 680/76, 1047/74; Surveys by: Jerry Lee Gamble, John R. Marshall, L. Peter Dinan, Wade B. Morgan, R.L. Daniels, Robert G. Watts, Hitchens Engineering & Surveying, Karl C. Mawhorter, Raymond M. Roberts, Landmark Surveys.

Description and plat by Landmark Surveys, Earl R. Donaker, Professional Surveyor, #7142, from a survey of the premises in the month of April, in the year of our Lord one thousand nine hundred and ninety-one.

DESCRIPTION APPROVED
FOR AUDITOR'S TRANSFER

BY J. L. Nauha
4-23-91

**OFFICE COPY
NOT RECORDABLE**

LANDMARK SURVEYS

727 Cambridge Road
Chesterton, Ohio 43812

THIS PROPERTY IS SUBJECT TO ALL EASEMENTS, RIGHTS-OF-WAY, OR RESTRICTIONS, WHETHER RECORDED OR IMPLIED.

tel: (614) 623-0993
1-800-842-3264



- NOTES:
- Also see a plat of 54.901 Ac. +/-, February, 1991, Thelma S. Neibarger
 - All bearings & distances are measured except as marked otherwise.

Pertinent documents, tax maps, Deeds: 1043/621, 1012/250, 752/263, 1019/77, 574/735, 786/37, 1001/410, 971/72, 753/105, 906/176, 492/150, 1033/265, 834/308, 1030/424, 1041/73, 590/54, 1028/568, 1028/565, 805/38, 848/229, 680/76, 1047/74

Surveys by: Jerry Lee Gamble, John R. Marshall, L. Peter Dihan, Wade B. Morgan, R.L. Daniels, Robert G. Watts, Hitchens Engineering & Surveying, Karl C. Mawhorter, Raymond M. Roberts, Landmark Surveys


Bearings are based on Deed Book 1047, p. 74.

- O - All 5/8" steel pins set are 30" long
- IP - iron pin found
- WP - water pipe found
- ST PIN - steel pin found
- RB - rebar found
- △ - pins to be set
- X - Loth set on line

DESCRIPTION APPROVED FOR AUDITOR'S TRANSFER

BY *Earl R. Donaker*
4-23-91

FRED & LOVINA HERSBERGER
DEED BOOK: 1047/74
SECTION W 1/2, NW 1/4, 7
2 QUARTER T. 1 N., R. 9 W., UNITED STATES MILITARY LANDS.
TOWNSHIP: HOPEWELL
COUNTY: MUSKINGUM
Date: APRIL, 1991



NOTE: EACH TRACT IS PART OF PARCEL #: 25-16-07-07

OFFICE COPY NOT RECORDABLE

I, Earl R. Donaker, Surveyor, certify this plat to be a true and correct survey pursuant to Chapter 177, Administrative Code, and to be the best of my knowledge and belief.

Remove not the old landmark" Deeds 28.10